Home Survey Inspection Report

Level 2 Home Survey

15 Example Avenue, Anytown, AN1 2YT

Property Address	15 Example Avenue, Anytown, AN1 2YT
Client Name	Mr & Mrs Sample Client 4
Inspection Date	1 July 2026
Report Generated	10 October 2026, 9:30 AM

This report is for the sole use of the named client and should not be relied upon by any third party.

Table of Contents

1 About Inspection 5 items

2 About Property 22 items

3 E Outside Property 11 items

4 H Grounds 4 items

5 F Inside Property 10 items

6 G Services 8 items

7 I Issues 3 items

8 J Risks 6 items

9 Capture floor/site plan sketches 1 items

About Inspection

Party Disclosure

I am not aware of any conflict of interest in this instruction as defined by the current RICS Valuations Professional Standards incorporating the RICS Valuation - Global Professional Standards and the RICS Rules of Conduct. Should any conflict become apparent before completion of the inspection or report, you will be informed immediately.

Weather

Weather: At the time of my inspection, the weather was cold, following a period of cold weather. Weather conditions can influence the visibility of certain defects, particularly those associated with roof coverings, rainwater goods, and dampness.

Property Status

Status: At the time of my inspection, the property was partly occupied. The property was fully furnished, and floor surfaces were partly covered, which limited inspection of concealed areas.

OverAll Opinion

In my opinion, the property represents a poor proposition for purchase at the agreed price, subject to the findings and recommendations contained within this report. Future maintenance and repair should be anticipated in accordance with the property's age, construction, and level of ongoing maintenance.

Reasonable with repair: This property is believed to be a reasonable proposition for purchase, given that you are prepared to cover the costs and accept the inconvenience of dealing with any repairs or improvement works reported. These defects are considered normal in properties of this age and construction. Provided that the works are carried out to a good standard, I cannot foresee any problems regarding a future resale of the property in normal market conditions.

Property Facing

Orientation: The front elevation of the property faces approximately south. References to orientation within this report assume the reader is standing facing the front of the property.

About Property

Property Type

Property type: The property is a detached, semi-detached, end-of-terrace, mid-terrace, converted flat, maisonette, bungalow and cottage providing four bedrooms.

Property Built

Year built: The property is understood to have been built in 1965. This assessment is based on available information, the apparent age and style of construction, and a visual inspection only. Unless documentary evidence is available, the stated age should be regarded as an approximation. Where the construction date cannot be confirmed, the age assessment is based upon the property's apparent style and construction.

Year built: The property is understood to have been built in 1970–1989. This assessment is based on available information, the apparent age and style of construction, and a visual inspection only. Unless documentary evidence is available, the stated age should be regarded as an approximation. Where the construction date cannot be confirmed, the age assessment is based upon the property's apparent style and construction.

Year Extended

Extended: The property has been extended to provide side, rear, single-storey, two-storey, roof and loft accommodation. The extension appears compatible with the original building in terms of construction and appearance. This assessment is based on a visual inspection only, and no opening-up or verification of concealed construction was undertaken. Your legal adviser should confirm that all necessary statutory approvals, including planning permission, Building Regulations approval, and any completion certificates or guarantees, have been obtained where required.

Year Converted

Converted: The property has been converted from its original use. The property was a semi-detached house, mid-terrace house, end-terrace house and sample detail 4, which has been converted to self-contained units.

Unknown date: The date of conversion is unknown. Your legal adviser should verify that all appropriate statutory approvals and completion certificates were obtained.

Flat Maisonettes

Flat information: The property is located on the second floor of a four storey building. The property is accessed via a private door to the side elevation of the property.

Accommodation

The accommodation comprises: Lower ground, Ground, First, Second, Third, Other and Roof space. The accommodation schedule contained within this report is provided for identification purposes only.

Floor	Living	Beds	Bath / shower	WC	Kitchen	Utility	Conserv.	Other
Lower ground	2	2	2	2	2	2	2	2 sample detail 4
Ground	2	2	2	2	2	2	2	2 sample detail 4
First	2	2	2	2	2	2	2	2 sample detail 4
Second	2	2	2	2	2	2	2	2 sample detail 4

Third	2	2	2	2	2	2	2	2 sample detail 4
Other	2	2	2	2	2	2	2	2 sample detail 4
Roof space	2	2	2	2	2	2	2	2 sample detail 4

Construction

Type: The property is believed to be constructed using solid wall, cavity wall, timber frame, steel frame, precast concrete panels, system-built and sample detail 4 construction.

Modern Building Design: The building is believed to be of a modern design, framed externally with timber, steel, or other materials, but most of the framework is concealed on both sides by cladding. The durability of the structure is dependent upon the care taken during construction. For this reason, I cannot comment on the condition of the concealed structure, given the limited scope and technique of the inspection. Please be aware that any alteration to this type of building will require specialist advice from a qualified person. The exterior of the property must be adequately maintained to prevent water penetration. It is also important to reduce the risk of condensation that might encourage damage or weaken concealed components. When improving insulation, you should ensure that the material used is appropriate. You can only install insulation within the wall cavity with specialist advice.

Roof type: The main roof is of pitched, flat and mansard construction formed with prefabricated trussed rafters and sample detail 4 structural members.

Roof cover: The roof covering is formed in clay tiles, concrete tiles, natural slate, artificial slate, metal sheeting, mineral felt, rubber membrane and single-ply membrane.

Other: sample detail 4

Internal walls: Internal walls are formed in timber stud partitions, lath and plaster and sample detail 4.

Floors: Floors are of solid concrete, beam and block and sample detail 4 construction.

Windows: Windows are fitted with timber, PVCu, steel and sample detail 4 frames incorporating double, triple glazing and secondary glazing, where applicable.

Listed Building

Listed building: No

Energy

Energy performance: According to the available Energy Performance Certificate: Energy Efficiency Rating: E. Potential Rating: E. This information has not been independently verified.

Location

Location: The property is situated within a modern residential development, mixed residential and commercial area, rural location, conservation and suburban location.

Density: The surrounding development is considered high.

Facilities

Facilities: Local amenities observed within reasonable proximity include shops, medical facilities, bus services, train stations and sample detail 4. The availability, quality and suitability of local amenities have not been investigated as part of this inspection.

Remote area - The property is in a remote area and likely to be far away from some of the usual facilities and amenities. Also, because of the location of the property, it is recommended that you contact the utility company to be certain regarding the nature of the drainage connection.

Local Environment

The property is in a location that could be affected by electromagnetic fields from an electricity substation or pylons located near the property. In addition to being unsightly, it may cause noise and disturbance, or interference may deter some future buyers, thus limiting saleability. The possible effects of electromagnetic fields have been the subject of media coverage. The Health Protection Agency (HPA), an independent body with responsibility for advising on electromagnetic fields, has advised that following the studies in 2000 and 2001, there may be risks, in specified circumstances, to the health of certain categories of people. Public perception may, however, affect marketability and future value of the property. If required, technical information can be obtained from the HPA or local electricity company.

The property is situated close to the sea, river, a canal, reservoir, or in a low-lying area, and may be susceptible to occasional or seasonal flooding. Your legal adviser should make further enquiries and advise you whether the building has been flooded in the past or is at risk of flooding. Enquiries should also be made to the Environment Agency.

Local environment: I observed the following environmental feature(s) that may influence your enjoyment of the property, its future marketability or materially affect the subject property: Susceptible to flooding, Railway line, Busy road, Commercial premises, Public house, School, Electricity substation, Overhead power lines, Airport flight path and sample detail 4. Where environmental concerns exist, you should make your own enquiries before legal commitment.

Private Road

Road: The property is located on an adopted public road, private road, cul-de-sac and unmade road. Where the property is situated on a private road, your legal adviser should confirm maintenance responsibilities and any associated financial liabilities.

Noisy Area

Noise: The property is located adjacent to, or close to, train lines or a station, commercial premises, industrial premises, public open space and schools. Such features may influence future enjoyment or marketability and should be considered before purchase.

Area

Conservation area: The property is suspected to be in an established conservation area. Your legal adviser should advise you on the implications of the property being situated in this location.

Garden

Front garden: The front garden is laid to lawn, artificial lawn, paving, timber decking, stones, hardstanding and sample detail 4.

Rear garden: The rear garden is laid to lawn, artificial lawn, timber decking, gravel, stones and hardstanding.

Fencing: Boundaries are formed by timber fencing, block wall, hedging, wire mesh, concrete sections and sample detail 4.

Communal garden: The communal garden is laid to artificial lawn, paving, timber decking, gravel, hardstanding and sample detail 4.

Fencing: Boundaries are formed by timber fencing, brick wall, block wall, hedging, concrete sections, metal railings and sample detail 4.

Topography

Topology: The property occupies steeply sloping ground.

Area Parking

Type: The property comes with residential, private, allocated, off-street, underground facility and sample detail 4 parking.

Front Garden

Front garden: The front garden is laid to lawn, artificial lawn, timber decking, gravel, stones and hardstanding.

Fencing: Boundaries are formed by timber fencing, block wall, hedging, wire mesh, concrete sections and sample detail 4.

Rear Garden

Fencing: Boundaries are formed by timber fencing, brick wall, hedging, wire mesh, concrete sections and metal railings.

Communal Garden

Communal garden: The communal garden is laid to lawn, artificial lawn, paving, timber decking, stones, hardstanding and sample detail 4.

Ground Parking

No Parking: The property does not come with parking.

Paid parking: Pay and display parking operates in the immediate area.

Gated Community

Gated: The property is located within a gated development and accessed via security-operated or access-controlled gates.

E Outside Property

Limitations

My inspection of the exterior was carried out from ground level and other reasonably accessible positions.

My inspection was restricted by the surrounding elements, including the layout of the area, and available vantage points from which I was able to view the property.

Limitations: The inspection was limited by height, restricted access, nearby buildings, vegetation, roof configuration and health and safety considerations.

Restricted Access: There was no direct access to the rear of the building. For this reason, I cannot make any detailed comments regarding the condition of the uninspected walls, roof slopes, rainwater goods, etc. You should accept the risk that some defects may exist in these unseen areas.

Roof coverings, chimney stacks, and high-level elements were inspected using binoculars where appropriate. No parts of the building were opened up, dismantled, or assessed. Where elements were concealed or inaccessible, no comment can be made regarding their condition.

Chimney Stacks

Not Applicable: The property does not incorporate the element(s) referred to in this section. No further comments are necessary.

Not Inspected: The chimney stack(s) could not be inspected due to access restrictions and the height and configuration of the building. Consequently, I am unable to comment on their composition or condition. As the roof is exposed to the weather, it should be inspected regularly and maintained as necessary to identify and address any defects at an early stage.

Description: The chimney stack(s) are constructed of brick, stone, rendered masonry and sample detail 4. The chimney stack(s) appear original. Pots: The chimney stack(s) are fitted with clay pots, terracotta pots, cowls, caps and sample detail 4. Number: The property has multiple stacks(s).

Location: The chimney stack(s) are located to the front, rear, centre and sample detail 4.

Flashings: The waterproofing between the chimney stack and the roof covering (called the flashing) appears to be formed in lead, mortar, bricks, tiles and sample detail 4. Condition: Where visible, the flashings appear in defective condition. Defective flashings may allow water penetration and should be repaired by an appropriately qualified roofing contractor. Flaunching: The cement bedding around the base of the chimney pot (called flaunching) appears to be formed in mortar, bricks, tiles and sample detail 4. Condition: Where visible, the flaunching appears in defective condition. Defective flaunching may permit water penetration and reduce the stability of chimney pots. Repairs should be undertaken as part of routine maintenance or sooner where deterioration is significant. Pointing. Condition: The mortar joints to the chimney stack appear in good, reasonable, weathered, eroded and sample detail 4 condition(s). Weathered or eroded pointing should be renewed to reduce further deterioration and water penetration. Damaged chimney pots: The chimney pots appear secure, cracked, damaged, missing and sample detail 4. Damaged or insecure chimney pots should be repaired or replaced to maintain weather resistance and safety.

Condition: Where visible, the chimney stack(s) appear in poor condition, consistent with their age and construction.

No repair: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine inspection and maintenance should be expected as part of normal property ownership.

Shared chimney: The chimney stack is believed to be shared with the neighbouring property or properties. The owner of the neighbouring property or properties may have some legal rights over this shared chimney. Your legal adviser should confirm ownership, maintenance responsibilities and any legal rights affecting the shared structure.

Leaning chimney: The chimney stack appears slightly leaning. Where significant movement is evident, further investigation by an appropriately qualified structural engineer or roofing contractor is recommended before legal commitment.

Repair required: At present, the observed chimney movement appears significant, and action is required now. You should contact a qualified person to inspect the chimney and recommend remedial action, which may involve rebuilding the chimney.

Not fully inspected: The chimney stack(s) could not be fully inspected because of height, restricted access, adjacent buildings and roof configuration. I cannot fully comment on their condition. Comments are limited to those areas visible from accessible inspection positions.

Removed chimney or pots: The chimney stack(s) or pots to the rear, side and centre have been altered and covered over with roofing. You should ask your legal adviser to confirm whether the removed chimney stack(s) received appropriate statutory approvals where required from the local council and advise on the implications.

Aerials and satellite dishes: An aerial and a satellite dish are attached to the chimney stack. Where secure, no action is currently required. Chimney Defects: One or more chimney defects were observed, including: missing flashings, cracked flaunching, missing mortar, spalled bricks, loose chimney pots, broken chimney pots, vegetation growth, open flues and loose satellite dish fixings. Repairs should be undertaken by an appropriately qualified roofing contractor to prevent further deterioration and water penetration.

Repair flashing: The waterproofing between the chimney stack and the roof covering is damaged or defective. This should be repaired now, depending on the severity of the defect. The roof covering and chimney stack may have to be disturbed to repair the flashing, and this can increase the extent of the work.

Causing damp: This is causing damp penetration to the adjoining building elements.

Repair flaunching: The cement bedding around the base of the chimney pot (called flaunching) is damaged or defective. This should be repaired soon. The roof covering and chimney stack may have to be disturbed to repair the flashing, and this can increase the amount of the work. The owner of the neighbouring property may have some legal rights over the shared chimney. You should check with your legal adviser before any work is done.

Repair pot: One or several pots fitted to the main building chimney stack are broken and partly missing. To replace the pot, you will have to renew the cement bedding around the base, called the flaunching, which holds the pot in place. The chimney pot may also be connected to a chimney flue that serves a heating appliance below, and a suitable replacement must be used.

Repointing: Some of the mortar between the bricks or stonework (called pointing) is damaged or defective. This should be repaired soon. The roof covering and chimney stack may have to be disturbed to repair the flashing, and this can increase the amount of the work.

Poor chimney condition: The chimney stack(s) on the front, side and centre of the building are in poor condition. This is a safety hazard. Although this can be repaired, it may be economical to rebuild the whole stack. This should be done now. If the chimney is no longer used by heating appliances below, it may be economical to reduce the chimney height to below roof level and extend the roof covering over it.

Repair now: This is a safety hazard, and the aerial/satellite dish may fall to the ground or on people. Where loose or inadequately fixed, repairs should be carried out promptly to prevent damage during adverse weather.

Repair aerials and satellite dishes: An aerial or satellite dish attached to the property is loose, rusted, damaged and dangling.

Repair aerials and satellite dishes: An aerial or satellite dish attached to the property is loose, damaged, dangling and sample detail 4.

Condition rating is: 3.

Significant defects requiring urgent repair or further investigation were identified. Appropriate remedial works should be undertaken without delay. Where the extent of the defect cannot be determined during a visual inspection, further investigation by an appropriately qualified person is recommended before legal commitment.

sample detail 4

You should ask the management company whether any repairs to the chimney stack(s) have been carried out previously or are currently proposed. Your legal adviser should confirm responsibility for repairs to the chimney stack(s) with the management company and ensure that an adequate sinking or reserve fund is in place to meet the cost of future repairs or replacement, should the need arise. This may help reduce the risk of unexpected repair costs or increases in the service charge.

Roof Covering

Wet weather: It was raining at the time of inspection; leaks and defects are more likely to be detected when it is raining.

Description: The pitched roof covering to the main building, porch, bay window and sample detail 4 is formed in original clay tiles, replacement clay tiles, concrete tiles, natural slate, fibre cement slates, aluminium sheets, composite slate and asbestos sheet.

Condition: Where visible, the covering appears in poor condition. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The roof covering appears to be adequately performing its function. Routine maintenance appropriate to the age of the roof covering should be expected.

Old roof covering: The roof covering over the building is old and may have reached, or be nearing, the end of its useful life and will need to be stripped and renewed soon. If re-covered in heavier materials the timbers may need to be strengthened to comply with current Building Regulations. Further, although functioning satisfactorily, older roof coverings should be expected to require increased maintenance and eventual replacement as part of their normal service life.

Asbestos: Parts of the roof covering and verge may contain asbestos. This type of asbestos base product is not normally a cause for concern according to the Health and Safety Executive. However, it should not be disturbed, sanded, or drilled without taking suitable safety precautions. When the slates are eventually replaced, a licensed removal contractor will need to be instructed, and this could be costly. Therefore, quotations for this work should be obtained before purchase commitment. Because of the possible asbestos content, you should get advice from a contractor experienced in this type of work or an asbestos specialist before any work is carried out.

Flat roof coverings: The flat roof covering over the building is formed in mineral felt, high-performance felt, rubber membrane, GRP fibreglass, asphalt, fibreglass and lead.

Condition: Where visible, the covering appears in poor condition.

Flat felt roof coverings have a comparatively short life and will require regular maintenance checks. Even though the general condition of the felt may appear satisfactory for its type and age, repairs or replacement must be expected in the future. It is difficult to predict when this will be required as felt roofs can break down with little warning, even when visually appearing sound.

No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The flat roof covering appears to be adequately performing its function. Routine maintenance appropriate to the age of the roof covering should be expected.

Old roof covering: The flat roof covering over the building is old and may have reached, or be nearing, the end of its useful life and will need to be stripped and renewed soon. If re-covered in heavier materials, the timbers may need to be strengthened to comply with current Building Regulations. Further, although functioning satisfactorily, older roof coverings should be expected to require increased maintenance and eventual replacement as part of their normal service life.

Description: The mansard roof covering to the main building, extension, porch and bay window is formed in original clay tiles, replacement clay tiles, natural slate, artificial slate, fibre cement slates, aluminium sheets, asbestos sheet and sample detail 4.

Description: The sample detail 4 roof covering to the extension, porch, bay window and sample detail 4 is formed in original clay tiles, replacement clay tiles, concrete tiles, artificial slate, fibre cement slates, aluminium sheets, composite slate and sample detail 4.

Flashings: The waterproofing at the junction of the roof covering and wall (called the flashing) appears to be formed in lead, mortar, clay tiles, mineral felt, lead substitute and sample detail 4. Condition: Where visible, the flashings appear in defective condition. Defective flashings should be repaired to reduce the risk of water penetration. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of the roof covering should be expected.

Ridge tiles: The covering along the top of the roof structure, called the ridge tiles, is assumed to be formed in clay and sample detail 4.

Condition: Where visible, they appear in defective condition. Loose or defective ridge tiles should be rebedded or mechanically fixed as appropriate. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of the ridge tiles should be expected.

Hip tiles: The covering along the junction of the roof slopes, called the hip tiles, is assumed to be formed in clay and sample detail 4.

Condition: Where visible, they appear in defective condition. Repairs should be undertaken where movement or deterioration is evident. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of the hip tiles should be expected.

Valley Gutters: The valley gutters are formed in mortar and sample detail 4.

Condition: Where visible, they appear in blocked condition. Blocked or defective valley gutters should be cleared, repaired, or replaced as necessary to ensure effective drainage and prevent water penetration into the building. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of the guttering should be expected.

Parapet walls: The parapet wall(s) are constructed of brick, stone, rendered masonry and concrete.

Coping: The parapet coping is formed in stone, tiles, engineering brick, metal and sample detail 4.

Condition: Where visible, these elements appear in defective condition. Defective copings or pointing should be repaired to prevent water penetration. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of the wall should be expected.

Roof line deflection: Minor undulation or deflection to all, front and rear roof slopes were observed. Such distortion is not uncommon in properties of this age and, unless accompanied by evidence of progressive movement, is not necessarily of structural significance.

Repair defect: The surface of the front and side roof slope(s) of the building is significantly distorted, uneven or undulating. You should contact a qualified roofing contractor to replace damaged timber or strengthen any weakened or undersized timber so that the roof structure can adequately bear the weight of the roof covering (see section J1 - Risk to Building).

Repair now: One or more tiles, slates, roof covering sections are severely or significantly loose, lifted, slipped, cracked, broken and sample detail 4. Given the extent of the defect, this should be repaired now. The fixings on older roofs can weaken and result in more future maintenance. In some cases, it may be economical to replace the whole roof covering rather than continuing to repair. You should contact a qualified roofing contractor to carry out further investigation and recommend remedial work.

Roof Spreading: The roof slopes to all, side and rear of the building appear uneven or undulating, and the adjoining wall appears distorted, cracked, bowing or leaning outwards. These are visual indicators that may be consistent with roof spread and suggest that the roof timber structure may require strengthening. I recommend that you instruct a suitably qualified structural engineer or roofing specialist to carry out further investigation and advise on any necessary remedial work without undue delay (see section J1 - Risk to Building).

Repair Flat roof: The flat roof covering is weathered, blistered, split, torn, ponding, damaged and sample detail 4. Causing damp - The observed defect is causing damp penetration to the building below. The flat roof covering needs repair or replacement now. To do this, the work will have to meet the requirements of the Building Regulations. This may increase the amount of repair work (see section J1 - Risk to Building).

Repair parapet: The copping, flashing and sample detail 4 of the parapet(s) of the roof are damaged, loose, partly missing, cracked and sample detail 4. This should be repaired now. Adjacent parts of the roof covering may have to be disturbed to repair the verge tiles, and this can increase the amount of repair work.

Safety hazard: This is a safety hazard, and parts of the parapet wall may fall to the ground and cause injury to people or property damage (see section J3 - Risk to People).

Repair verge: The mortar, slates, clips, caps and sample detail 4 items along the edge of the roof, called the verge, are damaged, cracked and loose. This should be repaired soon and, if significant, repaired promptly. Adjacent parts of the roof covering may have to be disturbed to repair the verge, and this can increase the amount of repair work. This should be repaired soon.

Repair valley gutters: The valley gutter at the junction of the roofs to all, front and rear of the building is blocked and has loose mortar. This should be repaired soon. Adjacent parts of the roof covering may have to be disturbed to repair the gutter, and this can increase the amount of repair work. This should be repaired soon.

Repair flashing: The waterproofing at the junction of the roof covering and wall is damaged or defective. This should be repaired soon. The roof covering may have to be disturbed to repair the flashing, and this can increase the amount of the work. The owner of the neighbouring property may have some legal rights over the shared chimney. You should check with your legal adviser before any work is done.

Causing damp: This is causing damp penetration to the adjoining building elements, and you must arrange to repair this urgently. Further defects and damage may be revealed from an intrusive or closer inspection by a qualified person.

Repair ridge tiles: The covering along the top of the roof structure called, the ridge tiles, is damaged or defective. This should be repaired soon. The roof covering may have to be disturbed to repair the flashing, and this can increase the amount of the work. The owner of the neighbouring property may have some legal rights over the shared chimney. You should check with your legal adviser before any work is done.

Repair hip tile: The covering along the slope of the roof structure (called the hip tiles) is damaged or defective. This should be repaired now. The roof covering may have to be disturbed to repair the flashing, and this can increase the amount of the work. The owner of the neighbouring property may have some legal rights over the shared chimney. You should check with your legal adviser before any work is done.

Not Inspected: The roof covering(s) could not be inspected due to access restrictions and the height and configuration of the building. Consequently, I am unable to comment on their composition or condition. As the roof is exposed to the weather, it should be inspected regularly and maintained as necessary to identify and address any defects at an early stage.

Condition rating is: 2.

Defects requiring repair or maintenance were identified. Although these are not considered urgent, repairs should be carried out to prevent further deterioration.

sample detail 4

General maintenance: Roof coverings should be inspected periodically, particularly following severe weather. Routine maintenance, including replacement of isolated defective coverings, clearance of debris and localised repairs, should be expected throughout the life of the roof.

Rain Water Goods

Wet weather: It was raining at the time of inspection; leaks and defects are more likely to be detected when it is raining.

Description: The rainwater goods comprise uPVC, aluminium, steel, concrete and asbestos cement gutters, downpipes, hoppers, and associated fittings.

Condition: Where visible, the rainwater goods appear in poor condition, consistent with their age and type. No parts of the rainwater installation were dismantled or tested. The adequacy of underground drainage has not been assessed as part of this inspection. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The rainwater goods appear to be adequately performing their function. Routine maintenance appropriate to the age and type of the rainwater goods should be expected.

The rainwater goods contain asbestos cement. Because of the possible asbestos content, you should get advice from a contractor experienced in this type of work or an asbestos specialist before the pipes or gutters are disturbed in any way. This includes activities such as cleaning out gutters, etc.

Shared Rainwater Goods: The rainwater goods are believed to be shared with the adjoining property. Your legal adviser should confirm ownership, maintenance responsibilities and any rights or obligations affecting the shared installation (See Section **I3**).

General Maintenance: Rainwater goods should be inspected and cleared at regular intervals, particularly during the autumn and following severe weather. Routine maintenance will assist in preventing blockages, overflow, water penetration, and premature deterioration.

Blocked Gutters: Vegetation, moss, leaves, or other debris were observed within sections of the guttering. The gutters should be cleared as part of routine maintenance to maintain effective rainwater disposal.

Blocked Gullies: One or more drainage gullies serving the rainwater system appear partially blocked. Blocked gullies may result in localised flooding and water penetration to adjacent building elements. The gullies should be cleared and maintained regularly.

Rainwater runoffs: Some rainwater pipes have not been connected to gullies or extended sufficiently away from the building and allowed to drain directly to the ground. Rainwater can penetrate nearby structures and potentially cause internal dampness, timber rot, or erosion around the building. The discharge arrangement should be reviewed and improved where appropriate.

Damaged Sections: Sections of the gutters or downpipes are cracked, distorted, broken, missing and sample detail 4. This should be repaired soon. Repairs or replacement should be undertaken to maintain the weather resistance of the building.

Insufficient slope: The slope on the guttering is too shallow. This prevents the rainwater from draining properly and may result in future leaks. The gutters should be refitted with an adequate slope soon. You may have to replace parts of the system, and this can increase the amount of repair work.

Defective Connections: One or more gutter or downpipe joints and connections are loose, missing, displaced, defective and sample detail 4. This should be repaired now. Repairs should be undertaken to maintain the effectiveness of the rainwater system.

Corrosion: Sections of the rainwater goods exhibit significant corrosion. Corroded sections should be repaired or replaced where necessary to maintain satisfactory performance. This should be repaired promptly if the damage is significant.

Condition rating is: 1.

The element(s) are performing their intended function, and no significant defects were observed. Routine maintenance appropriate to the age and construction should be expected.

sample detail 4

Main Walls

The external walls to sample detail 4 comprise a mixture of solid brick wall, cavity brick wall, cavity stud wall and sample detail 4 construction. The different wall types should be considered separately when planning future maintenance or alterations.

Description: The external walls of the main building and extension(s) are constructed of cavity blockwork. Condition: Where visible, the walls appear in poor condition, consistent with their age and type of construction. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The external walls appear to be adequately performing their function. Routine maintenance appropriate to the age and construction of the building should be expected. Painted Walls: The external wall surfaces, or parts of them, have been painted. Painting masonry can reduce its ability to breathe, trapping moisture within the wall. Rainwater may penetrate through fine cracks in the paint but be unable to evaporate freely, increasing the risk of dampness, frost damage and spalling of bricks or render over time. High internal humidity can also contribute to moisture becoming trapped within the wall construction. Painted external masonry also requires regular maintenance, as the finish will deteriorate and require periodic preparation and repainting to maintain its weather resistance and appearance. When future redecoration is undertaken, breathable masonry paint should be used where appropriate to minimise the risk of moisture becoming trapped.

Description: The external walls of the main building and sample detail 4 are constructed of rendered masonry. Condition: Where visible, the walls appear in poor condition, consistent with their age and type of construction. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The external walls appear to be adequately performing their function. Routine maintenance appropriate to the age and construction of the building should be expected.

Description: The external walls of the main building, extension(s) and sample detail 4 are constructed of pebble dash masonry. Condition: Where visible, the walls appear in poor condition, consistent with their age and type of construction. No repair required: No significant defects requiring immediate attention were identified unless otherwise stated below. The external walls appear to be adequately performing their function. Routine maintenance appropriate to the age and construction of the building should be expected. Painted Walls: The external wall surfaces, or parts of them, have been painted. Painting masonry can reduce its ability to breathe, trapping moisture within the wall. Rainwater may penetrate through fine cracks in the paint but be unable to evaporate freely, increasing the risk of dampness, frost damage and spalling of bricks or render over time. High internal humidity can also contribute to moisture becoming trapped within the wall construction. Painted external masonry also requires regular maintenance, as the finish will deteriorate and require periodic preparation and repainting to maintain its weather resistance and appearance. When future redecoration is undertaken, breathable masonry paint should be used where appropriate to minimise the risk of moisture becoming trapped.

Cladding: The external wall finish or cladding comprises natural or reconstituted stone, timber cladding, plastic panelling boards, weatherboarding, uPVC cladding, fibre cement panels, composite cladding panels, glass curtain walling, aluminium cladding panels, terracotta cladding tiles and sample detail 4.

EWS1 Cladding: The external walls are partially cladded with a brick-slip, brick-effect outer face, rainscreen boards, compressed composite boards, aluminium panels, glass reinforced concrete (GRC) panels, glass curtain walling and aluminium cladding panels, etc. This type of construction typically comprises fixing the cladding materials to a metal support frame secured to the primary structure, with a ventilated cavity and non-combustible mineral wool insulation behind. The inner leaf is commonly formed of concrete, blockwork or a metal framing system incorporating sheathing board and plasterboard lining. EWS1 form not required: Based on the visual evidence available during my inspection, the external wall construction appears broadly consistent with a building that may satisfy current EWS1 requirements. However, this inspection did not include an assessment of the external wall system for fire safety compliance, and I am not qualified to certify compliance. Confirmation can only be provided following an assessment by a suitably qualified fire safety professional, where required, and the issue of a valid EWS1 form. Your legal adviser should make further enquiries of the seller or managing agent and obtain a copy of any current EWS1 form, together with details of any planned, ongoing, or completed fire safety or cladding remediation works before you exchange contracts or commit to the purchase. This inspection should not be relied upon as confirmation of compliance with current fire safety legislation or lender requirements. Neither the surveyor nor this practice accepts liability for any loss, costs or delays arising from the fire performance of the external wall system, the absence or content of an EWS1 form, or any current or future remediation works or associated costs.

Moisture metre readings: Random moisture readings were taken to accessible internal wall surfaces using a hand-held electronic moisture meter. Damp found: Elevated moisture readings were recorded to sections of the internal wall surfaces that include sample detail 4. Penetrating damp cause: This may have been affected by penetrating damp probably caused by overflowing gutter, roof leak, leaking downpipe, blocked gully and sample detail 4. When the problem has been resolved, the wall may need to be repaired. Repair options: The source of the moisture should be identified and remedied as a priority. This may involve repairs to the roof covering, downpipes, damp-proof course, blocked gullies and sample detail 4, as appropriate. Once the source of moisture has been eliminated and the affected walls have been allowed sufficient time to dry naturally, any damaged plaster, decorations or other finishes should be repaired or replaced, as necessary. The affected area should then be monitored to ensure that the dampness does not recur. Investigate cause: The source of moisture cannot be confirmed during a visual inspection. You should instruct a suitably qualified contractor to investigate the cause of the dampness and carry out any necessary repairs to prevent further moisture penetration. Following completion of the repairs, the affected walls should be allowed to dry before any replastering, redecoration or replacement of finishes is undertaken. Premature redecoration may result in the recurrence of staining or damage if residual moisture remains within the wall. Rising damp: The wall(s) may be affected by rising damp. Probable causes include a damaged, deteriorated or bridged damp-proof course (DPC), high external ground levels, defective drainage, or other factors. The source of the moisture should be identified and remedied by a suitably qualified contractor. Once the cause has been addressed, any damaged plaster, decorations or other affected finishes may require repair or replacement.

Damp-proof course: The walls have a barrier against dampness rising from the ground (called a damp-proof course or DPC is visible; one would normally be expected for a property of this age and type. The DPC is assumed to consist of plastic, felt, engineering bricks and sample detail 4. The adequacy of concealed damp-proof courses cannot be confirmed during a visual inspection.

DPC Treatment noted: I noted evidence of wall ventilation apparatus, ventilation holes and sample detail 4 in the property. You should ask your legal adviser to check whether there has been a dampness problem before and if a valid guarantee or warranty covers this work. If not, you should ask an appropriately qualified person to inspect the property, assess its condition, and identify what repairs are required. Once the repairs have been completed, this person should issue a certificate of ‘structural worthiness.’ You should ask your insurance company if this problem would affect your ability to get insurance cover for this property.

Removed wall: An external wall to the kitchen, bedroom and sample detail 4 appears to have been removed as part of previous alterations. This work should have been carried out with Building Regulations approval and should have included adequate structural support for the remaining wall above the openings. Due to the internal floor and ceiling finishes, I was unable to confirm whether suitable structural support has been provided. I strongly recommend that your legal adviser obtains confirmation that the necessary Building Regulations approval was obtained for these alterations. If the required approval cannot be confirmed, or the work was not properly supervised, there is a risk that additional structural support may be required. This could result in further investigation, remedial works, additional costs, and disruption. Defect noted: I noted cracking, distortions and sample detail 4 in the surrounding wall surfaces. However, due to the concealed nature of the structure behind the wall and the floor and ceiling finishes, I was unable to confirm whether adequate structural support has been provided. You should instruct a suitably qualified structural engineer to carry out further investigation and advise on the adequacy of the structural alterations and any remedial works that may be required.

Extensions and alterations: Evidence was noted that external alterations have been carried out to the property. These include wall removal, new openings, replacement lintels, structural alterations and sample detail 4. Your legal adviser should confirm that all appropriate statutory approvals and completion certificates have been obtained where required.

Recent defects: The front, side and rear walls of the main building, back addition, extension, bay window, porch and sample detail 4 areas have been damaged by movement cracks potentially arising from settlement, subsidence, nearby vegetation, point loading, wall tie damage and sample detail 4, and this is considered structurally significant. Movement within the property is considered serious and could worsen over time. Parts of the property could become unstable. You should instruct an appropriately qualified structural engineer to investigate the problem and recommend an appropriate scheme of repair. To carry out a proper investigation, it is likely that parts of the property will need to be opened or disturbed, and this should be discussed with the building owner. Evidence of previous structural movement, even where satisfactorily resolved, may affect the property's future mortgageability and saleability.

Thin wall: The external wall to the front, rear and side walls of the extension and sample detail 4 is not thick enough and vulnerable to damp problems and heat loss. This substandard construction should be improved soon. In some cases, rebuilding the wall to modern standards may be the only economic option.

Cavity Wall Insulation: There is evidence that cavity wall insulation has been installed. Your legal adviser should verify the type of insulation used, the date of installation, and whether any guarantees or warranties are available. If it is confirmed that foam cavity wall insulation has been installed, please note that this type of insulation has been associated with problems in some properties. These may include deterioration of the insulation over time, allowing moisture to bridge the cavity and resulting in internal dampness, or contributing to the accelerated corrosion of wall ties where conditions are conducive. The availability of any guarantees or warranties should also be confirmed.

Trees: There are trees located close to the property. I noted no obvious signs to suggest that they have caused significant damage to the property. However, it would be prudent to implement a programme of management to control their future growth. Trees can affect building foundations and below-ground services, particularly where shrinkable subsoils are present.

Spalled Brickwork: A few bricks exhibit moderate deterioration (this is called spalling). Damaged bricks should be replaced where deterioration is sufficient to affect the weather resistance of the wall.

Repair render: Parts of the render coating to the building are cracked, eroded, loose and damaged. The defective pointing should be renewed using a mortar appropriate to the age, type, and construction of the building. This may comprise lime-based mortar or Portland cement mortar, as appropriate. Weathered or defective pointing should be renewed as part of routine maintenance to help reduce water penetration and minimise further deterioration.

Hazard: Rendering pieces are likely to fall and cause harm to people who may be nearby. This is a hazard, and this repair should be carried out urgently.

Causing damp: This is allowing damp to get into the building. These should be repaired now. Repair pointing: The mortar between the bricks (known as the pointing) to parts of the building is eroded, cracked, loose, missing, damaged, other. The defective pointing should be renewed using a mortar appropriate to the age, type, and construction of the building. This may comprise lime-based mortar or Portland cement mortar, as appropriate. Weathered or defective pointing should be renewed as part of routine maintenance to help reduce water penetration and minimise further deterioration. Causing damp: This is allowing damp to get into the building. These should be repaired now. Repair render: Parts of the render coating to the building are cracked, eroded, loose, missing, damaged. The defective pointing should be renewed using a mortar appropriate to the age, type, and construction of the building. This may comprise lime-based mortar or Portland cement mortar, as appropriate. Weathered or defective pointing should be renewed as part of routine maintenance to help reduce water penetration and minimise further deterioration. Hazard: Rendering pieces are likely to fall and cause harm to people who may be nearby. This is a hazard, and this repair should be carried out urgently. Causing damp: This is allowing damp to get into the building. These should be repaired now.

Repair pointing: The mortar between the bricks (known as the pointing) to parts of the building is eroded, cracked, loose, missing and sample detail 4. The defective pointing should be renewed using a mortar appropriate to the age, type, and construction of the building. This may comprise lime-based mortar or Portland cement mortar, as appropriate. Weathered or defective pointing should be renewed as part of routine maintenance to help reduce water penetration and minimise further deterioration.

Causing damp: This is allowing damp to get into the building. These should be repaired now. Repair pointing: The mortar between the bricks (known as the pointing) to parts of the building is eroded, cracked, loose, missing, damaged, other. The defective pointing should be renewed using a mortar appropriate to the age, type, and construction of the building. This may comprise lime-based mortar or Portland cement mortar, as appropriate. Weathered or defective pointing should be renewed as part of routine maintenance to help reduce water penetration and minimise further deterioration. Causing damp: This is allowing damp to get into the building. These should be repaired now.

Repair defect: Some signs may be consistent with defective cavity wall ties. Defective wall ties can affect the stability of cavity walls if left untreated. You should instruct a suitably qualified specialist to conduct a detailed inspection, confirm the condition of the wall ties, and recommend any necessary remedial works. Your legal adviser should also establish whether any guarantees or warranties are available in relation to previous repairs, if applicable.

Lintel defect: The lintel (the beam supporting the masonry above a door or window opening), including a brick arch where applicable, in the front, side and sample detail 4 wall of the main building, extension, bay window and sample detail 4 is damaged, cracked, or distorted.

Minor defects: The defects observed are limited and do not require significant repair. Where appropriate, cracks should be filled, defective pointing repaired, and any localised defects made good to help restore the integrity of the lintel or brick arch. Repairs should be carried out in the near future to prevent further deterioration.

Lintel defect: The lintel (the beam supporting the masonry above a door or window opening), including a brick arch where applicable, in the side, rear and sample detail 4 wall of the main building, back addition, extension and bay window is damaged, cracked, or distorted.

Windowsill defect: The windowsill(s) to the side, rear and sample detail 4 wall of the main building, back addition, extension and bay window is damaged, rotten, distorted and sample detail 4.

Significant Defect: The windowsill(s) is significantly damaged or defective and may be allowing water penetration into the building. Prompt repair or replacement by a suitably qualified contractor is recommended. Associated repairs to the surrounding masonry or window frame may also be required.

The external walls have been inspected visually and by touch from the outside and internally where exposed. No opening up or destructive investigation has been undertaken. The composition of the wall material cannot be fully confirmed without causing damage to the walls. Condition rating is: 3. Significant defects requiring urgent repair or further investigation were identified. Appropriate remedial works should be undertaken without delay. Where the extent of the defect cannot be determined during a visual inspection, further investigation by an appropriately qualified person is recommended before legal commitment. sample detail 4 You should ask the management company whether any repairs to the external walls have been carried out previously or are currently proposed. Your legal adviser should confirm responsibility for repairs to the external walls with the management company and ensure that an adequate sinking or reserve fund is in place to meet the cost of future repairs or replacement, should the need arise. This may help reduce the risk of unexpected repair costs or increases in the service charge.

Windows

Description: The windows are formed of replacement, original, old, timber, old style timber sash, modern uPVC sash, modern timber sash, composite and sample detail 4 framed units. Glazing: The glazing comprises double glazing, triple glazing, secondary glazing and decorative glazing. No BS EN: No visible British Standard, BS EN, or other permanent safety markings were identified on the accessible glazing. The absence of visible markings does not necessarily indicate that safety glazing has not been installed. Where confirmation is required, your legal adviser should verify any available certification relating to replacement windows. Condition: Where visible and operated during the inspection, the windows appear in poor condition, consistent with their age and type. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the age of window material should be expected. The windows appear to have been fully replaced or partially replaced. Where replacement windows have been installed, your legal adviser should confirm that the installation was carried out under an appropriate FENSA, CERTASS, or Building Regulation approval scheme where applicable. Any available guarantees or warranties should also be obtained. Double-hung sash windows are expensive to maintain and tend to be ill-fitting and allow heat loss. From time to time, it is important to employ a joiner to inspect the sash windows, check the cords, and ease them before redecoration. This is best done in conjunction with the redecoration cycle. Glazing seals: The external sealant around the window frames appears in poor condition. Defective sealant should be renewed to reduce the risk of water penetration.

Roof Velux Windows: Type: The property incorporates roof skylights, Velux roof windows and sample detail 4. These are formed in timber, PVCu, aluminium and sample detail 4 construction with double and triple glazing. Condition: Where visible, they appear in poor condition.

Windowsills: The windowsills are formed in PVCu, timber, brick, tiles and sample detail 4 material. Condition: Where visible, they appear in poor condition. Repairs should be undertaken where deterioration is sufficient to affect weather resistance.

Sill projection: Externally, the windowsills beyond the face of the walls appear to project adequately beyond the face of the walls. The junctions between the window frames and the surrounding wall openings appear to be poorly sealed. These seals should be inspected regularly for cracking and repaired as necessary to prevent water ingress.

Operation: The windows selected for operation opened and closed with minor with resistance. Windows should be inspected and maintained regularly. Moving parts, hinges, locks, and drainage channels should be cleaned, lubricated, and adjusted where necessary. Timber windows should be redecorated periodically to maintain protection against weathering. Sealants should be inspected and renewed where deterioration becomes evident.

Defective Operation One or more windows were found to: stick during operation, fail to close correctly, fail to lock securely, require adjustment, have defective handles and have defective locking mechanisms. Repairs or adjustment should be undertaken to maintain security and weather resistance.

Failed Glazed Units: One or more double-glazed units exhibit internal condensation and failed seals. Although this does not usually affect structural performance, replacement of the affected glazing units should be anticipated.

Damaged Glazing: One or more panes are cracked, broken and damaged. Damaged glazing should be replaced to maintain safety, security, and weather resistance. Hazard: One or more panes are damaged, and this presents a health and safety hazard. The damage should be promptly repaired by a qualified professional.

Timber Windows: Where timber windows are present, localised weathering, minor decay and sample detail 4 issues may occur as part of their normal service life. Regular decoration and maintenance should be undertaken to prolong their lifespan.

Condensation: Some condensation was noted on the glazing at the time of inspection. Condensation is influenced by occupancy, heating and ventilation and does not necessarily indicate a defect with the windows.

Repair windows: The window(s) in the lounge, dining room, bedroom and kitchen have damaged lock(s), have missing lock(s), are badly worn, are rotten, have broken glass, have failed glazing, are severely damaged, present a safety or security risk and have other defects. Where the defects are minor and do not present a safety or security risk, repairs should be carried out soon to prevent further deterioration. Where the defects affect the weather-tightness, security, or safe operation of the windows, repairs should be undertaken without delay. Severely damaged windows should be repaired or replaced immediately.

Fire Trap Risk: The design of the window(s) does not provide a suitable means of escape in the event of a fire. The affected window(s) in the lounge, dining room, bedroom and study have no opening and a small opening, creating a potential safety hazard. To reduce this hazard, you should seek advice from an appropriately qualified person regarding suitable remedial measures.

Not every part of the windows was inspected in detail. The inspection was limited to those parts that were readily accessible without causing damage or moving furnishings. Only a representative sample of accessible windows was opened and closed during the inspection. Windows obscured by curtains, blinds, shutters, furniture, stored items, or fitted security devices could not be fully inspected. Double-glazed units cannot be assessed for thermal performance during a visual inspection. Condition rating is: 3. Significant defects requiring urgent repair or further investigation were identified. Appropriate remedial works should be undertaken without delay. Where the extent of the defect cannot be determined during a visual inspection, further investigation by an appropriately qualified person is recommended before legal commitment. sample detail 4

Outside Doors

Only a representative sample of accessible doors was opened and closed during the inspection. Doors obstructed by security devices, stored items, furniture, or other restrictions could not be fully inspected. The operation and performance of locks, alarms and security systems were not assessed. Not every part of the external doors was inspected in detail. The inspection was limited to those parts that were readily accessible without causing damage or moving furnishings.

Description: The property incorporates replacement, original, old, rear, side, patio, French and sample detail 4 doors.

The external doors are formed of timber, composite, aluminium, steel and sample detail 4 material.

Glazing: The glazed sections comprise single glazing, double glazing, triple glazing and sample detail 4. The presence of safety glazing cannot be confirmed by visual inspection unless permanently marked.

No BS EN noted: No visible British Standard, BS EN, or other permanent safety markings were identified on the accessible glazing. The absence of visible markings does not necessarily indicate that safety glazing has not been installed. Where confirmation is required, your legal adviser should verify any available certification relating to replacement windows.

Condition: Where visible and operated during the inspection, the doors appear in poor condition, consistent with their age and type. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the door material should be expected.

The doors appear to have been fully replaced or partially replaced. Where replacement doors have been installed, your legal adviser should confirm that the installation was carried out under an appropriate FENSA, CERTASS, or Building Regulation approval scheme where applicable. Any available guarantees or warranties should also be obtained.

Glazing seals: The external sealant around the door frames appears in poor condition. Defective sealant should be renewed to reduce the risk of water penetration.

Thresholds: The door thresholds appear in poor condition. Minor wear is consistent with normal use. Defective thresholds should be repaired where deterioration affects weather resistance or safe operation.

Operation: The doors selected for operation opened and closed with difficulty. Doors should be inspected and maintained regularly. Moving parts, hinges, locks, and drainage channels should be cleaned, lubricated, and adjusted where necessary. Timber doors should be redecorated periodically to maintain protection against weathering. Sealants should be inspected and renewed where deterioration becomes evident.

Security: The doors are fitted with multi-point locking, cylinder locks, night latches and combination of locking systems. The level of security appears reasonable based upon a visual inspection only. The effectiveness of locks and security devices has not been evaluated.

Defective Operation One or more external doors were found to: stick during operation, fail to close correctly, require adjustment, have damaged hinges, have defective locking mechanisms, be distorted, have localised decay and have damaged frames. Repairs or adjustment should be undertaken to maintain security, weather resistance, and ease of operation.

Timber Doors: Where timber external doors are present, localised weathering, paint deterioration, surface splitting and minor decay may occur as part of their normal service life. Regular decoration and maintenance should be undertaken to prolong their lifespan.

Patio and French Doors: The property incorporates sliding patio doors, French doors, bi-fold doors and sample detail 4. The running gear, hinges and locking mechanisms should be inspected and maintained periodically.

General Maintenance: External doors should be inspected and maintained regularly. Moving parts, hinges, locks, handles, and seals should be cleaned, lubricated, and adjusted where necessary. Timber doors should be redecorated periodically to maintain protection against weathering. Flexible sealants should be inspected and renewed where deterioration becomes evident.

Repair doors: The door(s) in the lounge, dining room, kitchen and sample detail 4 have missing lock(s), are difficult to open, are badly worn, are rotten, have failed glazing, are in disrepair, are severely damaged and present a safety or security risk. Where the defects are minor and do not present a safety or security risk, repairs should be carried out soon to prevent further deterioration. Where the defects affect the weather-tightness, security, or safe operation of the doors, repairs should be undertaken without delay. Severely damaged doors should be repaired or replaced immediately.

Condition rating is: 3.

sample detail 4

Conservatory and Porches

Conservatory: The conservatory(s) is located to the side, rear and sample detail 4 of the building. The walls comprise single-glazed, double-glazed, triple-glazed, uPVC framed, aluminium framed, steel framed and sample detail 4 wall sections.

Roof: The roof is formed in glass, solid insulated panels, roofing tiles and sample detail 4 materials.

Doors and Windows: The conservatory comprises single-glazed, double-glazed, triple-glazed, uPVC, aluminium and steel-framed door(s), and window(s).

Floor: The floor is of suspended timber and sample detail 4 construction, and the floor is covered with carpet, tiles, laminated flooring and vinyl covering(s).

Condition: Where visible and operated during the inspection, the doors appear in poor condition, consistent with their age and type. Conservatories require routine maintenance appropriate to their age and construction. Glazing, roof coverings, sealants, rainwater goods, and external decorations should be inspected periodically and repaired where necessary to maintain weather resistance and serviceability. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the conservatory material should be expected.

No BS EN noted: No visible British Standard, BS EN, or other permanent safety markings were identified on the accessible glazing. The absence of visible markings does not necessarily indicate that safety glazing has not been installed. Where confirmation is required, your legal adviser should verify any available certification relating to replacement windows.

Building Joint Defects: Defects were noted to the junction between the conservatory and the main building. The defects may include cracked mortar pointing, sealants and weatherproof junction details or other defects. Repairs should be carried out to maintain a weathertight seal and reduce the risk of water penetration and further deterioration.

Unstable Structure: Evidence of movement, distortion, or deflection was observed. Further investigation by an appropriately qualified contractor is recommended where structural movement appears significant.

Porch: The porch(s) located to the front, side and rear of the building. The walls comprise single-glazed, double-glazed, uPVC framed, timber framed, aluminium framed and steel framed wall sections.

Building Regulations: The porch appears to be a later addition to the property. Your legal adviser should confirm whether any necessary Building Regulation approval or exemption applies, together with any guarantees or warranties available.

Roof: The roof is formed in glass, polycarbonate sheets, solid insulated panels and roofing tiles materials.

Doors and Windows: The porch comprises single-glazed, triple-glazed, uPVC, timber and aluminium door(s), and window(s).

Floor: The floor is of solid concrete and suspended timber construction, and the floor is covered with timber, carpet, laminated flooring, vinyl and sample detail 4 covering(s).

Condition: Where visible and operated during the inspection, the doors appear in poor condition, consistent with their age and type. Porches require routine maintenance appropriate to their age and construction. Glazing, roof coverings, sealants, rainwater goods, and external decorations should be inspected periodically and repaired where necessary to maintain weather resistance and serviceability. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the porch material should be expected.

BS EN noted: Visible British Standard, BS EN, or other permanent safety markings were identified on the accessible glazing. The presence of visible markings indicates that safety glazing has been installed. Where confirmation is required, your legal adviser should verify any available certification relating to replacement windows.

Unstable Structure: Evidence of movement, distortion, deflection was observed. Further investigation by an appropriately qualified contractor is recommended where structural movement appears significant.

Repair porch: The porch door, window(s), roof, floor, wall(s) and rainwater goods are cracked, damaged, rotten, damp, have failed, are misted over and present a safety hazard. These defects should be repaired in the near future. However, where the defects are severe or extensive, repairs should be carried out immediately.

Not Applicable: The property does not incorporate the element(s) referred to in this section. No further comments are necessary.

Condition rating is: 1.

sample detail 4

E8 Other Joinery and Finishes

Condition rating is: 1.

Repair: The fascias, barge boards, verge clips, timber cladding and sample detail 4 to the main building, back addition, extension, garage and sample detail 4 are damaged, poorly secured, incomplete and missing. Repairs should be carried out as soon as practicable to restore their integrity and prevent further deterioration, moisture ingress, or the risk of sections becoming detached. Any decayed timber should be cut out and replaced, defective fixings renewed, and all exposed timber surfaces properly prepared, treated, and redecorated to provide long-term protection.

Hazards: The above defect is a safety hazard. This should be repaired now.

Not Inspected: The usual external works at eaves level (the edges of the roof where the guttering is fixed) could not be inspected due to the height and configuration of the building. Consequently, I am unable to comment on their condition. These elements are typically formed in timber and should be regularly inspected, maintained, and redecorated as necessary to protect them from weathering, prevent decay, and prolong their service life.

Timber Weathering: Exposed timber joinery exhibits significant weathering. Where deterioration is limited, routine preparation and redecoration should prevent further decay. Otherwise, where decay is advanced, localised repair or replacement may be necessary.

Timber Decay: Surface decay and timber deterioration was observed. The affected timber should be repaired or replaced, and the source of moisture addressed where necessary.

Defective Joinery One or more defects were observed, including: loose fascias, damaged bargeboards, open joints, defective fixings, weathered decoration, distorted joinery and minor impact damage Repairs should be undertaken to prevent further deterioration and maintain weather resistance.

Inspected: The usual external works at eaves level (the edges of the roof where the guttering is fixed) could not be inspected due to the height and configuration of the building. Consequently, I am unable to comment on their condition. These elements are typically formed in timber and should be regularly inspected, maintained, and redecorated as necessary to protect them from weathering, prevent decay, and prolong their service life. Inspected: Inspection was carried out from ground level and other reasonably accessible positions. High-level joinery was inspected using binoculars where appropriate. Concealed sections behind gutters, roof coverings or other finishes could not be inspected. No opening up or dismantling of components was undertaken. This section relates to external joinery and finishes not covered elsewhere within this report, including fascias, soffits, bargeboards, eaves joinery, verge clips, cladding, decorative timberwork, or other associated external finishes. Only those areas that were readily visible and safely accessible at the time of inspection have been assessed. Redecoration should be undertaken periodically in accordance with the manufacturer's recommendations and the exposure of the property.

Condition rating is: 2.

Description: The external eaves-level joinery comprises timber, aluminium, asbestos board, cement board, fibre cement and sample detail 4 materials. Localised repairs or redecoration should be undertaken where deterioration is evident. Routine inspection and maintenance appropriate to the material should be expected throughout its service life.

Decorations: The external painted or stained finishes appear in weathered condition. External decorations are intended to provide weather protection as well as appearance.

Condition: Where visible, these elements appear in poor condition, consistent with their age and construction. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the joinery material should be expected.

General Maintenance: External joinery should be inspected periodically as part of routine property maintenance. Timber components should be redecorated at appropriate intervals to maintain protection against weathering. Sealants, fixings, and joints should be inspected regularly and renewed where deterioration becomes evident. Prompt attention to isolated defects will help prevent more extensive repairs.

As this is a leasehold property, your legal adviser should confirm, before the exchange of contracts, the provisions within the lease relating to the maintenance and external redecoration of the building, including when such works are due to be carried out and who is responsible for the cost. You should also ask the management company whether any repairs or external redecoration works have been undertaken previously, whether any are currently planned, and whether any associated costs are likely to be payable by leaseholders.

E9 Other Outside Property

Description: Where applicable, the external communal areas comprise communal entrances, access roads, footpaths, landscaped areas, boundary structures, security gates, lighting, bin stores, cycle stores and sample detail 4.

Condition: Where visible, these appear in poor condition, consistent with their age and use. General wear associated with normal use was observed where appropriate.

Carport: The property incorporates a timber, steel and masonry carport.

Roof: The roof is of pitched, flat and lean-to construction and covered with tiles, slates, felt sheet, polycarbonate sheet and sample detail 4 material.

Walls: The walls or balustrades are formed in timber, steel, glass and aluminium materials.

Floor: The floor is formed in block paving, tarmac, gravel and sample detail 4 finish.

Condition: Where visible, the structure appears in poor condition. Routine maintenance appropriate to its age and construction should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the carport material should be expected.

Porch Canopy: The property incorporates a porch canopy constructed of timber, steel, plastic and sample detail 4 material.

Roof: The roof covering comprises tiles, felt, polycarbonate, plastic and sample detail 4 material.

Condition: Where visible, the canopy appears in poor condition. Repairs should be undertaken where deterioration affects structural stability or weather resistance. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the porch canopy material should be expected.

Roof Terrace: The property incorporates a roof terrace. The structure is formed in concrete, steel and sample detail 4 materials.

Roof: The roof is of pitched, flat and lean-to construction and covered with tiles, slates, felt, polycarbonate and sample detail 4 materials.

Walls: The walls or balustrades are formed in bricks, timber, glass, aluminium and sample detail 4 materials.

Floor: The floor is formed in concrete, block paving, tarmac and sample detail 4 finish.

Drains: The drains are laid with bitumen, felt and concrete, other appear well drained, poorly drained and obstructed. Poorly drained or obstructed drainage channels can allow rainwater to pond or overflow, resulting in water penetration into adjacent building elements, deterioration of finishes, and an increased risk of slips. Any defective, blocked, or damaged drainage channels should be cleared and repaired promptly to ensure they continue to function effectively.

Condition: Where visible, the structure appears in poor condition. Routine maintenance appropriate to its age and construction of the roof terrace should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the roof terrace material should be expected.

Balcony: The property incorporates Juliet balcony(s) formed in steel, aluminium, glass, other materials. Condition: Where visible, it appears in good, reasonable, fair, poor, very poor condition. Guarding should remain securely fixed and free from significant corrosion or damage. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the Juliet balcony material should be expected. Balcony: The property incorporates a timber, steel, concrete and cantilevered balcony(s).

Walls: The walls or balustrades are formed in bricks, timber, steel, glass and sample detail 4 materials.

Floor: The floor is formed in concrete, tarmac, gravel and sample detail 4 finish.

Drains: The drains are laid with bitumen, felt and sample detail 4 materials, other appear well drained, unobstructed and obstructed. Poorly drained or obstructed drainage channels can allow rainwater to pond or overflow, resulting in water penetration into adjacent building elements, deterioration of finishes, and an increased risk of slips. Any defective, blocked, or damaged drainage channels should be cleared and repaired promptly to ensure they continue to function effectively.

Condition: Where visible, the structure appears in poor condition. Routine maintenance appropriate to its age and construction should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the balcony material should be expected.

Juliet Balcony: The property incorporates Juliet balcony(s) formed in steel, aluminium, glass and sample detail 4 materials.

Condition: Where visible, it appears in poor condition. Guarding should remain securely fixed and free from significant corrosion or damage. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the Juliet balcony material should be expected.

External Staircase: The property incorporates an external staircase constructed of concrete, steel, timber and sample detail 4 materials.

Element (s): The handrails, landing, and steps are formed in steel, timber and sample detail 4 materials.

Condition: Where visible, the staircase appears in poor condition. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the staircase material should be expected.

Other External Structures: Other external structures include bin stores, garden walls, pergolas, gazebos, covered walkways and sample detail 4 ancillary structures.

Condition: Where visible, these appear in poor condition. Routine maintenance appropriate to their age and construction installation should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the installation material should be expected.

Retaining Walls: The property incorporates stone, concrete, gabion and timber retaining walls.

Condition: Where visible, these appear in poor condition. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the retaining wall material should be expected.

Defects noted: Evidence of movement, bulging, instability and sample detail 4 was noted to parts or all retaining walls. You should arrange for further investigation by an appropriately qualified person. Retaining walls are designed to support the considerable weight of the ground behind them. Where the retaining wall is in poor condition, it may no longer be performing its intended function effectively. Repairs or replacement can be costly, as any new retaining wall must be designed and constructed to adequately resist the retained ground. You should instruct an appropriately qualified structural specialist to inspect the wall without delay and provide recommendations for any necessary remedial works. Where the retaining wall is shared with, or forms a boundary with, a neighbouring property, responsibility for repair and maintenance may be shared or otherwise affected by legal rights and obligations. Before any work is undertaken, your legal adviser should investigate ownership, maintenance responsibilities and any associated rights or liabilities, and explain the implications to you.

Walls: The balcony, carport, staircase and sample detail 4 wall(s) are damaged, are unstable, have eroded render and sample detail 4. Repairs should be carried out as soon as practicable to prevent further deterioration and maintain their structural integrity. Any movement-related cracking should be investigated if considered progressive.

Repairs Roof: The flashing, roof tile, sheet, or slate covering of the roof over the carport, balcony, canopy and sample detail 4 is missing, slipped, cracked, in disrepair, leaking, damaged, poorly secured and sample detail 4. Repairs should be undertaken as soon as practicable by a competent roofing contractor to prevent water ingress, further deterioration, and the risk of loose materials becoming dislodged.

Floor: The floor surface, timbers, or decking of the balcony, carport, roof terrace and staircase floor is split, cracked and sample detail 4. The defective areas should be repaired promptly to maintain a weatherproof surface, prevent water penetration into the structure below, and reduce the risk of trip hazards.

Drains: The balcony, carport, roof terrace and staircase drains are too small, blocked, damaged and sample detail 4, resulting in rainwater ponding. Standing water can accelerate deterioration of the waterproof covering and increase the risk of water penetration into the building. The drainage outlets should be cleared, repaired, or upgraded as necessary to ensure efficient disposal of rainwater, and thereafter maintained regularly.

Metal Stairs: The surfaces of the steps or landing are split, cracked, partly rotted and rusted. Repairs should be carried out as soon as practicable to remove the safety hazard, prevent further deterioration, and maintain safe access.

Decorations: The decorations to the stairway are peeling, flaking, damaged and sample detail 4. The affected surfaces should be properly prepared and redecorated as soon as practicable. Where corrosion or timber decay is present, the underlying defects should be treated or repaired before redecoration.

Handrails: The handrail(s) of the balcony, Juliet balcony, terrace and stairs are inadequate, poorly secured, loose, corroded, rotten and damaged and may not provide adequate protection against falls. This presents a safety risk. The defective handrail(s) should be repaired, replaced, or redecorated with a suitably designed and securely fixed handrail that complies with current safety standards.

The inspection was limited to those parts that were safely accessible at the time of inspection. No opening up, testing or dismantling of concealed elements was undertaken. Comments relate only to the visible condition of the structures inspected. This section relates to external features not reported elsewhere within this report, including carports, porches, balconies, Juliet balconies, roof terraces, external staircases, retaining walls, communal areas, and other ancillary external structures. Only those elements that were readily visible and safely accessible at the time of inspection have been assessed.

Condition rating is: 1.

sample detail 4

General Maintenance: External ancillary structures should be inspected periodically as part of routine property maintenance. Rainwater disposal, structural stability, guarding, fixings, waterproofing and external finishes should be maintained to reduce the risk of deterioration and ensure continued safe use.

It is assumed that the common parts are maintained under appropriate maintenance contracts and are the responsibility of the management company. Your legal adviser should obtain full details and refer to Section **I3** – Issues for Your Legal Adviser. Your legal adviser should also confirm that the person responsible for managing the building has complied with all applicable statutory requirements relating to asbestos. Where communal facilities are provided, your legal adviser should confirm: the identity of the management company, responsibility for maintenance and repairs, current service charges and reserve fund contributions, any planned major works, and any outstanding maintenance liabilities.

Inadequate lock

Inadequate Lock: The locking arrangements to the rear, side, patio, sliding patio doors, bi-fold doors and sample detail 4, do not meet current security standards and present a security risk. The locks should be upgraded at the earliest opportunity to improve the security of the property.

H Grounds

Limitations

The inspection of the grounds was visual only. Underground services, buried structures, and concealed defects could not be inspected or confirmed as part of this inspection.

No inspection restrictions: There were no unusual restrictions affecting my inspection of the grounds within the apparent ownership of the property.

Restricted access: Access to the rear or external elevations of the property was not available. Consequently, I was unable to inspect or comment on the condition or composition of the rear grounds. Comments are limited to those external areas that were visible and accessible at the time of the inspection.

H1 Garage

Garage

Condition rating is: 3.

sample detail 4

Not Inspected: Because access keys were not provided by the vendor or estate agent, or the provided keys could not open the garage, I was unable to inspect the garage(s) and therefore unable to comment about the internal condition of the garage(s) and roof timber or structure.

Converted garage: The garage has been converted into habitable accommodation, a workshop and sample detail 4. The conversion was inspected visually only. Your legal adviser should verify that any necessary planning permission (where required), Building Regulations approval and completion certificates are available, together with any relevant warranties or guarantees.

Shared Garage Access: Your legal adviser should confirm the rights of access, maintenance responsibilities and any liabilities relating to the shared garage access.

Garage Floor: The garage floor is constructed of concrete and stone material. Minor cracking and surface wear are common and do not necessarily indicate structural movement.

Garage Doors: The garage is fitted with a manually, roller shutter, side-hinged door, rear or side door and sample detail 4 constructed of steel, timber, aluminium, GRP (fibreglass) and sample detail 4 material. The door(s) appeared serviceable at the time of my inspection. Routine maintenance is recommended.

Condition: Where visible, the garage appears in poor condition. Routine maintenance appropriate to the age and construction of the garage should be expected.

Flat felt roofs have a limited-service life compared with pitched roof coverings and require regular inspection and maintenance. Although the covering may appear satisfactory at the time of inspection, repairs or replacement should be anticipated as it approaches the end of its serviceable life.

The roof covering material appears to contain asbestos. If left in good condition and undisturbed, it presents a low health risk. However, any disturbance, repair or removal should only be undertaken following advice from a suitably qualified asbestos specialist. The presence of asbestos-containing materials may affect future marketability.

Garage Defects

Minor defects: Defects were noted in the garage, including cracked walls, rotten window frame(s), cracked glazing, a cracked floor and sample detail 4. Repairs are recommended in the near future to prevent further deterioration.

Significant defects: Serious defects were noted in the garage, including badly cracked or unstable walls, beetle infestation, damaged glazing, a badly cracked floor and sample detail 4. Prompt investigation and repair are required to address the defects and prevent further deterioration or safety risks.

Safety hazard: The current condition of some of the elements of the garage is a safety hazard. You should resolve observed issues now.

H2 Other

Other

Condition rating is: 3.

sample detail 4

Grounds: The subject property is set within undulating grounds.

Gardens

Description: The outside areas comprise rear garden, side garden, courtyard garden, terrace and sample detail 4.

Grounds: The surfaces comprise block paving, concrete, gravel, tarmac, composite decking, stone paving and sample detail 4. Where decking is installed, it should be inspected regularly as deterioration may create a safety hazard.

Condition: Where visible, the garage appears in poor condition. Routine maintenance appropriate to the age and construction of the garage should be expected.

No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below.

Hardstanding areas: The paths and hardstanding area appear reasonably level, and exhibit no unevenness and minor unevenness. Minor settlement is common and may be addressed during routine maintenance. Where areas of uneven paving, trip hazards, or surface deterioration are present, adequate repairs and removal of damaged sections should be undertaken where necessary to maintain safe use.

Large Outbuilding

Outbuilding: The property incorporates a large shed, annex, summer house, office and studio permanent structure (s).

Construction: The structure(s) is formed of bricks, timber, steel, prefabricated concrete, aluminium and sample detail 4 materials.

Roof: The roof is of flat, lean-to and sample detail 4 construction and is covered with clay tiles, concrete tiles, slates, felt, metal sheets and sample detail 4 material.

Floor: The floor is constructed of concrete, suspended timber, engineered timber and beam and block material. Minor cracking, shrinkage, and surface wear to concrete floors are not uncommon and do not necessarily indicate structural movement. The floor was inspected visually only, and concealed areas beneath floor coverings or finishes could not be examined.

Doors and windows: The outbuilding(s) are fitted with door(s) and/or window(s) formed of timber uPVC, metal and sample detail 4 framed units. These appeared serviceable at the time of my inspection. Routine maintenance is recommended.

Condition: Where visible, the building appears in poor condition. Routine maintenance appropriate to the age and construction of the outbuilding should be expected.

Shared Access

Grounds: The communal/shared garden is paved, lawned, artificially lawned, laid with stones, laid with tile chippings and sample detail 4.

Fence: The boundary fences are formed in timber, brick, wire mesh, hedges, shrubs and sample detail 4.

No Fencing: The communal/shared garden of the property does not have fencing.

Shared Areas: The property benefits from a shared garden, communal parking, communal gardens and shared pathways access.

Condition: Where visible, the shared areas appear in poor condition. Routine maintenance appropriate to the age and construction should be expected. Your legal adviser should confirm your rights of use, maintenance responsibilities and any associated obligations or restrictions.

Private road: The road serving the property appears to be private and may not be maintained at public expense. Your legal adviser should confirm its status, together with any rights of access, maintenance responsibilities, and associated liabilities.

Fence

Repair fence: Parts of the boundary fencing are cracked, broken, unstable, loose in places, severely damaged, rotten and missing in places. You should arrange to repair or replace the affected fencing soon. However. if the damage is significant, repair should be carried out promptly and may be expensive.

Shed

Sheds: There is brick, aluminium and sample detail 4 shed(s) located within the grounds of the property. The roof(s) are pitched, flat and sample detail 4, and covered with felt, tiles, metal sheets and sample detail 4 materials.

Condition: Where visible, the shed(s) appear in poor condition. Routine maintenance appropriate to the age and construction of the shed should be expected. However, where the shed is in poor condition, you should arrange to repair or replace the shed.

Outbuilding

Repair outbuilding: Parts of the shed, annex, summer house, office and studio permanent outbuilding are damaged, have broken parts, is rotted in places, have missing sections and sample detail 4. This should be repaired soon, and if the defects are significant or present a hazard, it should be promptly repaired.

Retaining Walls

Nearby Trees: One or more trees are located close to the property. Tree roots can, in certain ground conditions, influence foundations, particularly where mature trees are close to buildings and during prolonged dry periods.

Defects noted: One or more trees are located close to the property. Tree roots can, in certain ground conditions, influence foundations, particularly where mature trees are close to buildings and during prolonged dry periods. With groups of trees, the risk is usually greatest during prolonged dry spells. Detrimental effects on the property, fencing, outbuilding and sample detail 4 were noted that include subsidence movement. You should contact a qualified person for further investigation and advice. Also, the trees should be regularly pruned to restrict future growth and minimise the risk of further defects occurring.

H3 Other Area

Other Area

Condition rating is: 2.

sample detail 4

Right of Way: The property benefits from and/or is subject to shared rights of way over a private road, footpath, entrance lobby and sample detail 4. Your legal adviser should confirm the rights of access, maintenance responsibilities and any associated.

Knotweed

Not Found: No evidence of Japanese knotweed was observed within the areas inspected. However, the inspection was limited to those areas that were visible and reasonably accessible at the time of the survey, and its absence cannot be guaranteed. Recent gardening works, dense vegetation, or other ground cover may conceal evidence of invasive plants and prevent their identification during a visual inspection.

Management D: Japanese knotweed was observed on neighbouring land within approximately three metres of the property boundary. Although no damage was evident to the subject property, the infestation should be monitored, and your legal adviser should make appropriate enquiries where necessary.

Lifts: The building is served by one or more passenger lifts. These are specialist installations and were not inspected or assessed as part of this survey. Your legal adviser should confirm that appropriate inspection, maintenance, and servicing arrangements are in place.

Flooding: The property is in an area that may be at risk of flooding due to its proximity to a canal, the coast, low-lying land and reservoir. Your legal adviser should make appropriate enquiries and, where necessary, obtain an environmental or flood risk report.

EMF

electricity substation, high-voltage overhead power lines, pylons.

F Inside Property

Limitations

It was not practical to inspect parts of the property that were covered, concealed or otherwise inaccessible without causing damage or disturbance, such as lifting carpets or removing fixed fittings. Consequently, no assurance can be given regarding the condition of these concealed areas. This report relates only to those parts of the property that were reasonably accessible at the time of the inspection.

Where the roof space is inaccessible due to the absence of a suitable access hatch or the presence of other obstructions, I am unable to assess the type, presence, adequacy or condition of the insulation or concealed roof timbers. Where available, the Energy Performance Certificate (EPC) may provide additional information regarding the insulation within the roof space.

Moisture readings represent the condition of the property only at the time of the inspection and cannot provide absolute assurance that concealed surfaces or structural elements are free from moisture-related defects. Weather conditions, temperature, and humidity can all influence moisture levels and the observations made during an inspection. Where my findings are inconclusive regarding the extent or cause of dampness, I recommend that you arrange a further investigation by a suitably qualified independent specialist. The inspection should be carried out in accordance with the Joint Position Statement (JPS) 2022, Investigation of Moisture and its Effects on Traditional Buildings, and should be undertaken independently of any contractor providing quotations for remedial work.

Limitations: The inspection of the internal accommodation was limited by fitted floor coverings, furniture, fixed fittings, restricted access, locked rooms, limited roof access and health, and safety considerations.

Where roof space access was available, only those areas that could be inspected safely from the access hatch and boarded areas were examined. Insulation, stored items, roof timbers, and restricted headroom may have limited the inspection. Inaccessible areas have not been inspected.

Roof Not Fully Inspected: I could not fully inspect the roof timber because of floor was boarded, excessive storage, insulation and underlining at the time of my inspection. No comments can be made regarding unseen elements.

Unsafe floor: I could not fully inspect the roof timbers because the floor was unsafe to walk on at the time of my inspection.

F1 Roof Structure

The roof structure was inspected from the roof access hatch where available and from those areas that were safely accessible at the time of the inspection.

Condition rating is: 1.

sample detail 4

You should ask the management company whether any repairs to the roof structure have been carried out previously or are currently proposed. Your legal adviser should confirm responsibility for repairs to the rainwater goods with the management company and ensure that an adequate sinking or reserve fund is in place to meet the cost of future repairs or replacement, should the need arise. This may help reduce the risk of unexpected repair costs or increases in the service charge.

Loft converted: The original roof structure has been substantially altered to form the loft conversion, with most structural elements now concealed from view. Consequently, I am unable to comment on the condition of the concealed areas. Your legal advisers must verify that all necessary planning permissions, Building Regulations approvals, and required interim and final inspections were obtained for the conversion before you commit to the purchase.

Description: The roof structure is formed in traditional cut timber, steel and sample detail 4 construction.

Condition: Where visible, the roof structure appears in poor condition, consistent with its age and construction. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the roof structure material should be expected.

Evidence of Water Penetration: Water staining or dampness was observed on roof timbers, underlay, or adjacent structural elements. The source should be identified and repaired to prevent further deterioration.

Capped Soil Vent Pipe: A capped soil and vent pipe was noted terminating within the roof space. This arrangement is not considered appropriate, as any leakage or escape of foul gases could discharge into the roof space. The pipe should be inspected by a suitably qualified plumber to establish its purpose and condition. Where it forms part of the drainage ventilation system, it should be appropriately extended and terminated to the outside air in accordance with current requirements. Any redundant pipework should be removed or suitably sealed.

General Maintenance: Roof spaces should remain adequately ventilated and free from unnecessary stored items that may restrict inspection or ventilation. Roof timbers should be inspected whenever significant roofing works are undertaken. Prompt attention to water penetration will reduce the risk of timber decay and associated structural deterioration.

Water Storage Tanks: The roof space contains plastic, galvanised steel, asbestos cement and sample detail 4 cold water storage tanks.

Condition: Where visible, the tank appears in poor condition. No defects noted: No evidence of leakage or significant defects was observed at the time of inspection unless otherwise stated. Routine maintenance appropriate to the tank material should be expected.

Leaking: The water tank is leaking or in disrepair. You should repair or replace this promptly to prevent further dampness and damage to nearby elements.

Water Tank Insulation: The water tank and associated pipework appear partially insulated. Improving insulation may reduce the risk of freezing and heat loss. The absence of, or inadequate, insulation could result in condensation, dampness or leakage to the ceiling or surrounding areas.

Missing or Inadequate tank cover: The plastic, galvanised metal and asbestos cold water tank cover(s) are missing or inadequate. This should be replaced soon.

Disused Water Tank: Plastic, galvanised steel and sample detail 4 disused water storage tank(s) remain within the roof space. Removal may be considered during future maintenance where it is no longer required.

Wood Boring Noted: Evidence of active and historic wood-boring insect activity was observed. Further inspection by an appropriately qualified timber specialist is recommended where activity appears active or widespread. Otherwise, for historic activity, further enquiries should be made to the vendor regarding its history, treatment work, and guarantee certificates.

Timber Decay: Evidence of wet rot, dry rot and sample detail 4 timber decay was observed. The source of moisture should be identified and promptly rectified before repairs are undertaken. Ventilation to the roof space should be maintained to prevent conditions favourable to rot.

Thin Timbers: Parts of the original timber structure are too small, and this could affect the stability of the roof structure. You should ask an appropriately qualified person to inspect the roof and recommend a repair scheme.

Chimney Breast Alterations: Evidence was observed that a chimney breast has been partially removed, altered, rendered and sample detail 4 within the roof space.

Risk of collapse: Part of the chimney breast within the roof space has been removed, and the remaining structure is not properly supported and is at risk of collapse. This is a safety hazard. You should ask your legal adviser to check if the local authority gave permission for this work. Further, you should instruct a suitably qualified professional to inspect the structure and provide a report with any necessary recommendations as soon as possible.

Minor Chimney Damp: Minor dampness from water penetration was noted to the rendered chimney breast within the roof space. This is not uncommon in a property of this age and construction, as a damp-proof course would not normally have been provided to the chimney. The moisture is likely to have been exacerbated by defects in the flashing where the roof abuts the chimney stack. This is not considered a significant concern at present, but the flashing should be inspected and repaired if necessary, during routine roof maintenance or when the roof covering is next renewed.

Largely missing: The party wall within the roof space is missing, creating a risk of fire spread between this and the neighbouring property and reducing security between the properties. The wall should be rebuilt to the underside of the roof covering and all gaps appropriately fire-stopped without delay. As the party wall may be subject to legal rights and obligations under the Party Wall etc. Act 1996, you should consult your legal adviser before arranging any works, particularly where the proposed work may affect the adjoining property.

No Underlay: The absence of a roof underlay could result in water leakage, lower internal temperatures, higher heating costs, condensation, and mould growth. I recommend that you contact a qualified person to inspect the roof covering and confirm its watertightness.

Ventilation noted: The roof space appears to have limited ventilation. Adequate roof space ventilation assists in reducing the risk of condensation and timber decay. Where ventilation is limited, improvements should be considered when future roofing works are undertaken.

Thermal Insulation: The roof space floor insulation appears limited, insufficient, poorly fitted and sample detail 4 based upon the visible areas only. The thickness and continuity of insulation cannot be confirmed without disturbing the insulation. Reference should also be made to the Energy Performance Certificate where available.

Adequate insulation: The insulation to the loft floor appears adequate where visible. Where insulation is inadequate or absent, you should upgrade it to a depth of 270–300 mm to meet current recommended standards, taking care not to obstruct roof ventilation.

Roof Movement: Evidence of deflection, sagging and spread was observed. Observed roof movement is normal, minor, severe, presents a hazard and sample detail 4. Further investigation by an appropriately qualified roofing contractor is recommended where movement appears significant or presents a hazard.

Structural Alterations: Evidence of structural alterations to the roof space was observed, including loft conversion, altered roof members, removed struts, trimmed rafters, additional timber supports and sample detail 4 alterations. The adequacy of structural support cannot be confirmed during a visual inspection. Your legal adviser should confirm that appropriate statutory approvals and completion certificates were obtained where applicable.

Timber defects: Localised distortion, splitting, cracking, notching and sample detail 4 were observed. Repairs or further investigation should be undertaken where structural adequacy is uncertain.

Roof Not Fully Inspected: I could not fully inspect the roof timber because of limited roof height, the floor was not safe to walk on, floor was boarded, insulation, underlining and sample detail 4 at the time of my inspection. No comments can be made regarding unseen elements.

F2 Ceilings

The ceilings have been inspected from within the rooms only. No opening up or destructive investigation has been undertaken.

Condition rating is: 1.

sample detail 4

Description: The ceilings are formed in plasterboard, lath and plaster and sample detail 4 ceilings. The ceiling finishes comprise painted, textured coating, papered, timber-clad, wallpapered, decorative panelled and sample detail 4 finishes.

Condition: Where visible, the ceilings appear in poor condition, consistent with their age and construction. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the ceiling material should be expected.

The ceilings are fully or partially made of older plaster supported on thin wooden strips (called 'lath and plaster'), typical of properties built before the 1940s. While no significant defects were noted at the time of inspection, these ceilings can deteriorate with age as the plaster loses its bond with the timber laths. They are susceptible to vibration and disturbance, and localised repairs are likely to be required over time, particularly during redecoration or alteration works. Repairs can be difficult and may dislodge adjacent plaster, making complete ceiling replacement more economical in some cases.

Parts of the ceilings within the property may contain asbestos-containing materials. In their current condition, these are not normally considered a significant risk if left undisturbed. However, they should not be drilled, sanded, cut, or otherwise disturbed without appropriate precautions. If future refurbishment or replacement is planned, the material should be assessed beforehand and, if asbestos is confirmed, removed by a licensed contractor. This can add significantly to the cost of future works.

General Maintenance: Ceilings should be inspected periodically for signs of cracking, distortion, or water penetration. Prompt repair of roof leaks, plumbing defects and condensation problems will reduce the likelihood of damage to internal ceiling finishes. Routine redecoration should be expected throughout the normal life of the property.

Significant cracking: Significant cracking was observed in parts of the ceilings. Further investigation is recommended where cracking appears progressive or is associated with distortion.

Polystyrene Ceiling Tiles: Parts of the ceilings are covered with polystyrene tiles, which present a fire safety risk. Polystyrene is highly flammable and, if ignited, can contribute to the rapid spread of fire while releasing dense, toxic smoke and harmful fumes that can significantly increase the risk to occupants. Although these tiles may have been acceptable when installed, they no longer meet modern fire safety expectations. They should be removed as soon as practicable by a competent contractor. Be aware that removal may damage the underlying ceiling, particularly if the tiles have been firmly bonded, and repairs or complete replacement of the ceiling finish may be required.

Heavy decorative covering: The ceilings are covered with heavy lining paper, decorative finishes, or similar coverings. No significant defects were evident at the time of inspection; however, these finishes can conceal minor cracking or other imperfections. Their removal during future redecoration may damage the underlying plaster, and you should allow for localised repairs or re-plastering.

Minor unevenness: Minor bowing, undulations, unevenness and sample detail 4 were noted on the ceiling surfaces. These are not uncommon in properties of this age and do not necessarily indicate structural movement.

Dry water staining: Localised water staining was noted on the ceiling in the lounge, dining room, kitchen, bathroom and sample detail 4. Damage consistent with previous water penetration was observed. Although the affected area appears dry at the time of inspection, repairs and redecoration should be undertaken as required.

Ornamental plaster repair: The ceiling incorporates ornamental plaster features, some of which were found to be loose, cracked, damaged, partially missing and sample detail 4. These defects present a safety hazard, as sections may become detached and fall. A suitably qualified plastering contractor should inspect the affected areas and carry out appropriate repairs or replacement without delay. Localised repairs may be possible; however, where deterioration is extensive, complete replacement of the affected ornamental plasterwork may be necessary, resulting in more extensive and costly remedial works.

F3 Walls and Partitions

My inspection was limited by fixed furniture, kitchen units, bathroom fittings, large appliances, stored items, tiled finishes, decorative wall coverings, and fitted cupboards, which prevented full inspection of the concealed areas. The condition of hidden wall construction, lintels, structural supports, and other concealed elements could not be confirmed without opening the structure, which is outside the scope of a Level 2 Home Survey. No comment can be made on the condition of these concealed areas, and defects may exist that were not visible at the time of my inspection.

Condition rating is: 3.

sample detail 4

Description: The walls are formed in solid masonry, timber stud partitions, lath and plaster and sample detail 4 construction. The wall finish comprises plaster, wallpaper, tiling, timber panelling, decorative panelling and sample detail 4 finishes.

Condition: Where visible, the walls and partitions appear in poor condition, consistent with their age and construction. Routine redecoration appropriate to the age and condition of the property should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the wall material should be expected.

The walls are fully or partially made of older plaster supported on thin wooden strips, called lath and plaster, typical of properties built before the 1940s. While no significant defects were noted at the time of inspection, these walls can deteriorate with age as the plaster loses its bond with the timber laths.

Condensation: Evidence of condensation and localised mould growth was observed on wall surfaces, ceilings or window reveals, in the bedrooms, bathrooms, kitchens and sample detail 4 area(s). Condensation is commonly associated with occupancy patterns, heating, insulation, and ventilation. Maintaining a suitable balance between heating and ventilation should assist in reducing condensation. Extractor fans may be installed, and windows opened regularly.

Suspected rising damp: Elevated moisture readings were recorded at the base of the wall(s), consistent with possible rising damp, including the sample detail 4. Where fitted units, such as kitchen cabinets, conceal wall surfaces, the extent of dampness cannot be fully assessed, and any necessary remedial works may be more extensive and costly. I recommend further investigation by a suitably qualified damp specialist to confirm the cause and advise on any necessary repairs.

Minor cracking: Minor shrinkage or settlement cracking was observed in the wall finishes. Such cracking is common in properties of this age and type and is not considered structurally significant. The cracks may be adequately filled with appropriate material and redecorated during routine maintenance.

Internal Alterations: Evidence was observed that an internal wall has been partially removed, altered, new opening created and has been formed. Where an internal wall has been removed or altered, other parts of the property must be properly supported.

No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the building material should be expected.

Hollow Plaster: Localised areas of hollow-sounding plaster were noted. This usually indicates that the plaster has lost adhesion to the underlying surface. Although stable at the time of inspection, affected areas may become loose or detached over time. Localised repairs may be possible; however, where deterioration is more extensive, or the plaster becomes unstable, it may be more practical and cost-effective to remove and replace the affected section. Repairs can be undertaken as part of routine maintenance or redecoration, as necessary.

F4 Floors

The condition of concealed floor timbers, floor voids, joists, sleeper walls, and foundations cannot be confirmed without lifting floor finishes or opening the structure. Only the visible performance of the floors was assessed during normal use. The inspection was limited by fitted floor coverings, furniture, stored items, fixed kitchen units, bathroom fittings, or restricted access. The floor construction has been inspected from within the property only. Floor coverings were not lifted, and no opening up or destructive investigation was undertaken.

Condition rating is: 2.

sample detail 4

Description: The floors are formed in solid concrete, suspended timber and beam and block construction. The floor finishes comprise floorboards, carpet, ceramic tiles, laminate flooring, wood flooring, vinyl and sample detail 4 finishes.

Condition: Where visible, the floors appear in poor condition, consistent with their age and construction. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the flooring material should be expected.

General Maintenance: Because floor coverings were not lifted, concealed defects may exist that could not be identified during a visual inspection. No comment can therefore be made regarding the condition of concealed floor timbers or supporting construction. Floors should be inspected periodically for signs of movement, dampness, or deterioration. Prompt repair of plumbing leaks, water penetration and defective ventilation will reduce the risk of damage to concealed floor timbers. Floor finishes should be repaired or replaced as part of normal property maintenance when they reach the end of their service life.

Creaking floor noted: I walked over the accessible suspended floor surfaces and found them to be firm underfoot. Localised creaking and minor unevenness were noted in parts of the floors and/or stairs. These are not uncommon in properties of this age, and, at the time of inspection, there was no evidence of excessive springiness or significant distortion suggestive of structural failure. This is associated with normal shrinkage or movement between floorboards and joists. Repairs may be undertaken as part of routine maintenance.

Cracked Tiles: The floor tiles appear in good, reasonable, fair, poor, very poor condition. Where visible, the floor tiles in the kitchen, utility room, toilet, conservatory, porch and sample detail 4 areas showed no evidence of cracking at the time of my inspection. No repairs are currently required. Routine maintenance only is recommended. Cracked Tiles: Localised cracked, loose and damaged floor tiles to the kitchen, utility room, toilet, conservatory, porch and sample detail 4 areas were observed. Repairs should be undertaken to maintain the floor finish and reduce the risk of further deterioration.

Timber decay noted: Decay was noted to the floor timbers, bathroom floor, kitchen floor, basement floor joists and sample detail 4 areas. The full extent of the decay could not be determined during this visual inspection, and additional concealed defects may be present. Further investigation by a suitably qualified timber specialist is recommended, and you should obtain a report and quotations for any necessary remedial works before committing to the purchase.

Wood Boring Noted: Evidence of active wood-boring insect activity was observed in the property, lounge, bedrooms, kitchens and sample detail 4 areas. Further inspection of active activity by an appropriately qualified timber specialist is recommended where activity appears active or widespread. Otherwise, for historic activity, further enquiries should be made to the vendor regarding history, treatment work, and guarantee certificates.

Unknown damp cause: Although I could not see the full extent of the damp problem, I suspect more serious defects exist in hidden areas. You should ask an appropriately qualified person to inspect the floor and identify the full extent of the problems.

Underfloor Ventilation: Where applicable, the suspended timber floor is provided with adequate underfloor ventilation. Adequate ventilation is important in reducing the risk of condensation and timber decay. Where ventilation appears restricted or limited, improvements should be considered during future maintenance works.

Repair timber floor: The timber floor to the lounge, bedroom, kitchen, bathroom and sample detail 4 is broken, uneven, springy, loose, sloping, damp, insect infested, rotten and poorly ventilated, and the defect(s) is considered minor. This is common with floors of this age and construction, and these should be repaired soon. However, where the defect is significant, repair must be carried out promptly by a qualified professional.

Laminate/Wood floor defects: The laminate or wood flooring to the lounge, bedroom, bathroom, utility room, hallway and sample detail 4 areas are worn, damaged, poorly fitted, cracked, lifted and sample detail 4. These should be repaired or replaced soon.

Sloping floor: The floor to the lounge, bedroom, kitchen, utility room, hallway and sample detail 4 rooms are significantly sloping. This is commonly associated with long-standing settlement, historic movement, or deflection of the floor structure. Where the slope is slight, and there is no evidence of ongoing movement or associated structural defects, it is unlikely to be of structural significance, and no repairs are considered necessary. Where the slope is significant, or accompanied by cracking or distortion, further investigation by a suitably qualified building contractor is recommended to determine the cause and specify any necessary remedial works before purchase commitment.

F5 Fireplaces and Chimneys

This section relates to visible fireplaces, chimney breasts, and associated flues within the property. The inspection was limited to a visual assessment only. Fireplaces, flues, and appliances were not assessed, dismantled, or operated unless otherwise stated. The internal condition of chimney flues, liners and concealed structural elements cannot be confirmed during a visual inspection. No smoke testing, CCTV survey or opening up was undertaken. Combustion appliances should be provided with adequate permanent ventilation in accordance with current standards. The adequacy of ventilation has not been assessed during this inspection.

Condition rating is: 1.

sample detail 4

General Maintenance: Fireplaces, flues, and combustion appliances should be inspected and serviced regularly by appropriately qualified contractors. Unused flues should be adequately ventilated to reduce the risk of condensation and dampness. Where fireplaces are no longer required, appropriate capping and ventilation should be maintained.

Description: The property incorporates open fireplaces, gas fires, electric fires, solid fuel stoves, multi-fuel stoves and decorative fireplaces.

Condition: Where visible, the fireplace(s) and chimney breast(s) appear in poor condition, consistent with their age and construction. If the flues are to be used, they should be inspected and assessed by an appropriately qualified chimney specialist before use. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the fireplaces, chimney breasts and flues material should be expected.

Vented blocked fireplace: The fireplace(s) in the lounge, dining room, bedroom, hallway and sample detail 4 are vented.

Removed Chimney Breasts: Evidence was observed that a chimney breast has been partially removed and removed. The adequacy of concealed structural support cannot be confirmed during a visual inspection. Your legal adviser should confirm that appropriate Building Regulation approval and completion certification were obtained where applicable. Where structural adequacy is uncertain, further investigation by an appropriately qualified structural engineer is recommended.

Defects noted: The chimney breast has been removed from the bedroom, kitchen, bathroom, utility room and sample detail 4. The adjacent construction is damaged, distorted and sample detail 4. I saw evidence that indicates this has not been done properly. You should ask an appropriately qualified person to investigate this problem and recommend any repairs. This may involve removing parts of the floor and wall, and you should discuss this with the property owner.

Boiler Flues: Where a heating appliance discharges through an external wall or roof, the visible flue terminal appears secure, adequately positioned, and free from obvious obstruction. The installation has not been assessed.

Fireplace defects: One or more of the following defects were observed: cracked fire surround, damaged hearth, cracked chimney breast, distorted fireplace opening, localised damp staining and surface deterioration. Repairs should be undertaken where deterioration affects safety or continued use. If you plan to use the fireplace again, you should ask an appropriately qualified person to inspect and repair the fireplace. Although I do not know the full extent of the work required, you should plan for complete replacement. You should not use the fireplace until this has been done.

F6 Built In Fittings

The inspection was limited by stored items, fixed appliances, contents of cupboards, restricted access, or locked cupboards. Wall and floor surfaces concealed behind fitted units could not be inspected. No comment can therefore be made regarding the condition of concealed areas.

Condition rating is: 1.

sample detail 4

Worktop(s): The kitchen and sample detail 4 worktops comprise laminate particle board, granite, quartz, stone, Corian, marble, steel and sample detail 4 material.

Fittings: The kitchen, utility room and sample detail 4 units are formed in timber, vinyl-wrapped timber, laminated MDF and sample detail 4 materials.

Condition: Where visible, they appear in poor condition. Routine adjustment and maintenance should be expected with normal use. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the built-in fittings should be expected.

Kitchen Sink: The kitchen and utility room sink(s) is formed in stainless steel, ceramic, stone and sample detail 4 material. Where visible, it appears in poor condition. The sink was inspected visually only and was not assessed for leakage or drainage performance.

Built-in Appliances: The property incorporates oven, hob, extractor hood, microwave, refrigerator, freezer, washing machine and tumble dryer built-in appliances. These appliances have not been assessed. Their condition, safety and serviceability are outside the scope of this inspection.

Extractor Fan: The kitchen extractor fan was operating at the time of inspection. Its effectiveness cannot be confirmed without normal use. Regular cleaning of grease filters and vents should be undertaken to maintain efficient operation.

General Maintenance: Built-in fittings should be maintained as part of normal property ownership. Sealants should be inspected periodically and renewed where deterioration becomes evident. Cupboard hinges, runners, and door furniture should be adjusted or replaced where necessary. Water leaks should be repaired promptly to prevent damage to adjoining units and finishes.

Fittings defects: One or more cupboard doors or drawers require adjustment, repair, replacement due to wear or damage.

Sealant defects: The sealant around the sink or at the wall joints with the worktop is damaged, moulded, worn and missing. Defective sealant should be renewed to reduce the risk of water penetration into adjacent units.

Defects: One or more of the following defects were observed: loose hinges, damaged worktops, worn finishes, defective sealant, damaged plinths, water-damaged units, misaligned drawers and loose handles. Repairs should be undertaken as part of normal maintenance.

F7 Woodwork

Condition rating is: 3.

sample detail 4

General Maintenance: A representative sample of timber has been inspected, but the possibility of concealed defects being present in inaccessible timber cannot be ruled out completely. Internal woodwork should be inspected and maintained as part of normal property ownership. Moving parts should be adjusted and lubricated where necessary. Timber should be redecorated periodically to protect exposed surfaces. Any source of moisture should be addressed promptly to minimise the risk of timber deterioration.

Description: The joinery items comprise door frames, skirting boards, architraves, staircases, handrails, window boards, timber cladding, wardrobe(s), built-in joinery and sample detail 4 timber components.

Condition: Where visible and operated during the inspection, they appear in poor condition. Routine adjustment and maintenance appropriate to their age and construction should be expected. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the timber joinery should be expected.

Repair now: The staircase creaks and exhibits noticeable movement when in use, suggesting that joints or fixings may have become loose or that the supporting timber requires repair. Although the exact cause could not be confirmed during this visual inspection, the staircase should be inspected by a suitably qualified contractor, with any necessary repairs carried out without delay to ensure it remains safe and serviceable.

No handrails: The staircase has open risers (open treads), which present a safety hazard, particularly to young children, due to the risk of falling through or becoming trapped between the treads. Although open-riser staircases may have been acceptable when installed, they do not provide the same level of safety as modern enclosed staircases. A suitably qualified contractor should assess the staircase and install appropriate infill panels or other suitable guarding to improve safety. This work should be carried out without delay where young children are likely to occupy or visit the property.

Investigate: Some internal doors and frames are distorted, and the door(s) do not shut properly. I noted signs that suggest current or ongoing movement that warrants further investigation. You should instruct a suitably qualified structural engineer to inspect the building and provide a report with any necessary recommendations as soon as possible.

Rocking handrails: The staircase handrail, supported by timber balusters (spindles), was found to be loose and rocked when gently assessed. This is a safety hazard, as the handrail may fail if subjected to normal use or excessive force. Repairs should be carried out without delay by a suitably qualified contractor to securely fix the handrail and associated balustrade.

Door operation: The internal doors selected for operation opened and closed with resistance. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the timber joinery material should be expected.

One or more internal doors do not close properly or operate with resistance. This is commonly caused by normal wear and tear, minor distortion, settlement, or worn hinges, latches, or other ironmongery. In most cases, adjustment or minor repairs will restore satisfactory operation. Where defects are more severe or the door is damaged, replacement may be required. Repairs should be undertaken as part of routine maintenance.

Defect noted: One or more internal joinery elements, including doors, locks, door frames, skirting boards, the staircase, balustrades, handrails, window boards, cupboards, built-in joinery and sample detail 4, were found to be worn, loose, poorly fitted, damaged, missing, affected by decay and sample detail 4. Where the defects are minor, repairs can be undertaken as part of routine maintenance. Otherwise, where the defects are significant or affect safety, security or normal operation, repairs or replacement should be carried out without delay by a suitably qualified contractor.

Wood-Boring Insects: I found minor and significant evidence of historic wood-boring insect activity in parts of the staircase, floorboards, under stairs, cupboards and sample detail 4 in the sample detail 4. The extent of any concealed damage could not be determined during this visual inspection. Where activity is historic, no treatment may be necessary if the timber is dry and the infestation is inactive. Where active infestation is suspected, or significant timber deterioration is present, a suitably qualified timber specialist should inspect the affected areas, confirm the extent of the infestation, and carry out any necessary treatment and repairs without delay.

F8 Bathroom Fittings

The inspection was limited by stored items, fixed furniture, bath panels, boxed-in pipework, restricted access, or sealed fittings. Concealed plumbing, waste pipework, and waterproofing systems could not be inspected. No comment can therefore be made regarding concealed defects. The inspection was limited to a visual assessment only. Sanitary fittings, plumbing installations, and drainage systems were not dismantled or pressure assessed.

Condition rating is: 3.

sample detail 4

Description: The property incorporates a family bathroom(s), shower room(s), ensuite shower room(s), separate toilet(s), utility room and sample detail 4.

Sanitary ware: These are fitted with a combination of sanitaryware including a bathtub(s), shower(s), wash hand basin(s), WCs, mains pressure shower, electric shower, thermostatic shower, shower enclosure and sample detail 4 installation.

Wall finishes: Wall finishes comprise ceramic tiles, water-resistant wall panels, painted plaster and sample detail 4 finishes.

Condition: Where visible, the bathroom fittings appear in poor condition, consistent with their age and use. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the fittings should be expected.

General Maintenance: Bathroom fittings should be maintained as part of normal property ownership. Sealants should be inspected regularly and renewed where deterioration becomes evident. Adequate heating and ventilation should be maintained to reduce condensation and mould growth. Plumbing leaks should be repaired promptly to minimise water damage to adjoining finishes and concealed building elements.

Working extractor fan: The extractor fan(s) installed in the family bathroom(s), ensuite shower room(s), ensuite bathroom(s), separate toilet(s) and utility room were working at the time of inspection. The effectiveness of the fan(s) cannot be confirmed without the bathroom being in normal use. Where condensation or mould growth is evident, the fan should be cleaned regularly and set to continue operating after use, where this function is available, and window(s) opened regularly if one is available, to improve air circulation and ventilation.

Sealants: Sealant around the bath, shower tray, basin, and sanitary fittings appears in poor condition. Defective or deteriorated sealant should be renewed to reduce the risk of water penetration into concealed areas.

Defects: One or more of the following defects were observed: defective sealant, cracked sanitary ware, damaged wall tiles, damaged cubicle/screen, poor ventilation, condensation, mould growth, water staining, damaged bathtub panel and minor plumbing leaks. Repairs should be undertaken as part of normal property maintenance.

F9 Other

Condition rating is: 2.

sample detail 4

Description: Internal communal parts to the property comprise entrance lobby, hallway, landing, lift lobby, fire lobby, balcony, communal storage and sample detail 4.

Poor condition: The internal communal areas are in poor condition and require repairs, general maintenance, redecoration, refurbishment and sample detail 4. These defects may result in increased service charges or one-off contributions from leaseholders. Your legal adviser should confirm with the person responsible for managing the building whether these works are planned, how they will be funded, and whether any major expenditure is anticipated. I have assumed that the communal areas are subject to appropriate maintenance arrangements and are the responsibility of the management company or other responsible party. Your legal adviser should confirm the maintenance responsibilities, arrangements, and any associated service charge obligations. Your legal adviser should also confirm that the person responsible for managing the building has complied with all applicable statutory requirements relating to asbestos management.

Cellar/Basement Not inspected: The property has a cellar or basement, but it could not be inspected due to restricted access, no access and sample detail 4. No comment can therefore be made on its condition.

Walls: The property incorporates a cellar, basement and the walls are formed in bricks, stone, loose soil and concrete materials.

Floor: The floor is constructed of solid concrete, timber, loose soil and sample detail 4.

Condition: Where visible, the cellar appears in poor condition. Minor dampness may be expected in older cellars below ground level and does not necessarily indicate a defect. No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance is recommended.

In use: The cellar or basement has been adapted for use as storage or other uses. It appeared to be in reasonable condition at the time of inspection. Continue normal maintenance.

Unsuitable: The cellar or basement should not be regarded as habitable accommodation due to low headroom, dampness, poor ventilation and sample detail 4. It should only be used as ancillary storage space.

Flooded: The cellar or basement was partially flooded due to defective drainage or groundwater ingress. An appropriately qualified drainage or building specialist should investigate the cause and recommend remedial works.

Damp: Dampness was noted on the upper walls, throughout the cellar, exposed floor joists and sample detail 4. Further investigation by a suitably qualified damp and timber specialist is recommended to establish the cause and specify appropriate repairs.

Waterproofing failure: The extent of dampness suggests failure or absence of an effective waterproofing system. Remedial works are likely to be disruptive and potentially costly. You should ask a suitably qualified specialist to investigate and provide recommendations. Your legal adviser should also confirm whether any waterproofing guarantees or warranties remain in force.

Timber decay: Decay was noted in exposed floor joists within the cellar. This is a serious defect that may affect the structural integrity of the floor above. A suitably qualified timber and damp specialist should inspect the affected timbers and recommend appropriate repairs.

Repair: The entry stairs, balcony, hallway, shared lobby, fire lobby and sample detail 4 areas are worn, creaking, badly cracked, sloping, missing in places and sample detail 4. These should be repaired soon, and if the defect is considered significant, it should be promptly investigated by a qualified person and repaired.

G Services

Limitations

Services are concealed within the structure and cannot be fully inspected during a Home Survey. The inspection is visual only, and services are not assessed for safety, operation, efficiency, capacity, compliance with current regulations, or remaining service life. Comments are limited to the visible parts of the installation. Unless otherwise stated, services should be assumed to require routine maintenance appropriate to their age and use. Where there is any doubt about the condition or safe operation of a service installation, further inspection by an appropriately qualified specialist should be obtained before legal purchase commitment. It has been assumed that the necessary statutory compliance certificates, inspection records, and approvals are available where required. These documents have not been inspected as part of this survey and should be verified by your legal adviser before exchange of contracts. Where the condition or safety of a service installation cannot be assessed from a visual inspection, I may recommend further investigation by an appropriately qualified specialist and apply an appropriate Condition Rating. The inspection was limited by one or more of the following access restrictions, boxed-in services, stored items, fixed fittings, locked cupboards, floor coverings, or health and safety considerations. Concealed pipework, wiring, ductwork, and underground services could not be inspected.

G1 Electricity

sample detail 4

Metre: There is a mains electricity supply connected to the property, and the meter unit is located under the stairs, in the entrance hall, in the kitchen, in the garage and in a communal cupboard.

Metre not found: I did not find the electric meter. Please ask the vendor about the location of the mains electricity meter, as you must know where it is located.

Consumer unit: There is a consumer unit(s) installed under the stairs, in the kitchen, in the garage, in a communal cupboard and sample detail 4.

Not found: I did not find the consumer unit(s). Please ask the vendor about the location of the fuse box, as you must know where it is located.

RCD Protection: The consumer unit incorporates RCD protection, RCBO protection and no visible RCD protection. The operation of protective devices has not been assessed.

Dated or Old: The installation appears to comprise dated or older electrical components and would require upgrading to current standards.

General Maintenance: Where the installation appears dated, altered, or poorly maintained, an Electrical Installation Condition Report (EICR) should be obtained before legal commitment.

Solar photovoltaic (PV) system: The property is fitted with photovoltaic (PV) panels installed on the roof slope(s). These generate electricity for use within the property, with any surplus potentially exported to the National Grid. No significant defects were apparent from the limited visual inspection. Routine maintenance should be carried out in accordance with the manufacturer's recommendations.

Battery storage/Inverter: A solar battery and/or inverter is in the loft and under the stairs. These components were not assessed, and no comment can be made on their operation, performance, or remaining service life.

Electricity Repair

Poor Standards: The electrical system is below current standards because there are exposed wires, damaged fittings, DIY work and sample detail 4 issues, and this is a safety hazard. You should ask an appropriately qualified person to inspect the electrical system and carry out required repairs or replacement(s). Although I do not know the extent of the repair and improvement works required, you should plan for partial or complete replacement.

Electrical installations should be inspected and assessed at intervals not exceeding ten years for owner-occupied properties, or on a change of ownership, in accordance with current guidance. If satisfactory evidence of a recent Electrical Installation Condition Report (EICR) is unavailable, you should instruct an appropriately qualified electrician, such as a NICEIC or NAPIT registered contractor, to inspect and test the installation, confirm its condition and safety, and provide a quotation for any necessary remedial works.

Condition rating is: 3.

G2 Gas and Oil

Testing: The gas installation and appliances were not assessed during this inspection. If satisfactory evidence of recent inspection or servicing is unavailable, a Gas Safe (or OFTEC for oil-fired systems) registered engineer should inspect and test the installation before legal purchase commitment and recommend any necessary remedial works.

Certification: The homeowner should be able to provide appropriate servicing and inspection records for the heating system and associated appliances, including boilers, fires, and other fixed heating appliances. Your legal adviser should verify that these documents are available before exchange of contracts.

sample detail 4

Gas smell noted: Gas smell was noted during my inspection. This is a serious problem and should be resolved now.

Metre: There is a mains gas connection to the property, and the meter unit is located under the stairs, in an outside box, in the garage, in a communal cupboard and sample detail 4. No smell of gas was detected during my inspection, and no other defects were noted that require urgent or significant repairs to the installation.

Oil tank: The property is served by an oil-fired heating system with a metal and sample detail 4 fuel storage tank located at the side garden, rear garden and sample detail 4. No significant defects were apparent from the limited visual inspection, and routine maintenance is recommended. Oil-fired appliances, associated equipment and storage tanks should be installed, serviced, and inspected annually by an OFTEC-registered engineer. Where the tank is located close to a watercourse, open drain or environmentally sensitive area, secondary containment (a bund) may be required to reduce the risk of pollution in the event of a leak. Where there is any doubt regarding the condition, installation or compliance of the oil storage tank or associated equipment, an OFTEC-registered engineer should inspect the installation and recommend any necessary remedial works before legal purchase commitment.

Condition rating is: 2.

G3 Water

sample detail 4

Not found: There is an independent mains water supply to the property. I did not find the water stopcock within the property. Please ask the vendor about the location of the water stopcock, as you must know where it is located. The property must be maintained in the normal way.

The visible water supply pipework comprises plastic and/or copper. Much of the plumbing is concealed within the structure, and the routing, support, joints, and condition of hidden pipework could not be assessed during this visual inspection. If there are any concerns regarding the plumbing installation or its condition, you should obtain further advice from a suitably qualified plumber before legal purchase commitment.

Condition rating is: 3.

G4 Heating

sample detail 4

No heating: The property does not have a fixed heating system. Although no repair is currently required, the absence of fixed heating may result in cold rooms, condensation, and mould growth. It is also likely to adversely affect the property's Energy Performance Certificate (EPC) rating and may impact its marketability. You should consider installing a suitable fixed heating system.

Heating not found: I was unable to locate the boiler or heating system. Please ask the vendor about the location of the boiler or heating system, as you must know where it is located.

Communal heating: The property is heated centrally by a communal heating system. I could not inspect the system due to access restrictions and cannot comment on the type and condition.

Boiler: The property is heated by a combination boiler, conventional boiler, sealed boiler system, electrical boiler and sample detail 4 that is installed in kitchen, bedroom, under the stairs, garage and sample detail 4. The installation was inspected visually only. No operational testing or assessment of efficiency was undertaken.

Heat emitters: The boiler is connected to radiators, underfloor heating pipes, wall vents and sample detail 4 as heat emitters; their capacity, efficiency, and lifespan are not readily ascertained. I recommend these are serviced and demonstrated to yourselves, so you are satisfied with their performance under variable operational requirements.

Room heaters: The property is heated by oil-filled, electric storage, individual room electric and sample detail 4 heaters. These appear in reasonable condition. However, I cannot comment on their serviceability as the system was not operating at the time of my inspection and I have no evidence of any service history. The property must be maintained in the normal way.

Old boiler: Although no significant defects were apparent from the limited visual inspection, the boiler is older. Older boilers are less efficient and may become increasingly unreliable and costly to maintain. You should anticipate replacement as the boiler approaches the end of its serviceable life.

Forced Air Heating: The property is heated by a forced air heating system with the main unit located in the utility room, garage, cupboard, basement and sample detail 4. Warm air is distributed throughout the property via a network of ducts and vents. The installation was inspected visually only, and no operational testing or assessment of efficiency was undertaken. The property must be maintained in the normal way.

Air Source Heat Pump: Air Source Heat Pump: The property is heated by an air source heat pump with the internal unit located in the kitchen, utility room and sample detail 4 and the external unit located to the front and rear of the property. The installation was inspected visually only. No operational testing or assessment of performance, efficiency or controls was undertaken.

Ground Source Heat Pump: Ground Source Heat Pump: The property is heated by a ground source heat pump with the internal unit located in the kitchen, garage and sample detail 4. The associated ground collectors or boreholes are below ground and could not be inspected. The installation was inspected visually only. No operational testing or assessment of performance, efficiency or controls was undertaken.

Heating Repair

Repair: The radiator(s) and pipework in the lounge, bedroom, bathroom and sample detail 4 areas are leaking, damaged and sample detail 4 and may be causing damp to nearby elements. Although this is not yet serious, the problem can quickly get worse and damage other parts of the property. You should ask an appropriately qualified person to check this now and promptly resolve the situation. Where a significant leak has occurred causing damage to other parts of the property, this may indicate more widespread defects within the installation. A suitably qualified plumber/heating engineer should investigate the cause, carry out any necessary repairs, and inspect the remainder of the system without delay.

Any inspection, servicing or repair of the heating installation should be carried out by a Gas Safe registered engineer (or an OFTEC registered engineer for oil-fired systems). Appropriate servicing or commissioning records should be provided for the boiler, heating system, and any fixed heating appliances. Your legal adviser should verify that these records, together with any available warranties or guarantees, are available before legal purchase commitment.

Condition rating is: 1.

G5 Water Heating

sample detail 4

Not found. I was unable to locate the water heating system. Please ask the vendor about the location of the water heating system, as it is important that you know where it is located.

Communal water heating: The property has hot water centrally by a communal water heating system, gas-powered. It is likely to be metered or supplied as part of combined services. I could not inspect the system due to access restrictions and cannot comment on the type and condition.

Water heating: The hot water is provided by the conventional boiler, sealed boiler system, electrical boiler and oil-fired boiler installed in the airing cupboard, kitchen, bedroom, garage, loft and sample detail 4. The property must be maintained in the normal way.

Electric Immersion: The hot water is provided by an insulated cylinder located in the airing cupboard, kitchen, bedroom, garage, loft and sample detail 4. The installation was inspected visually only. No operational testing or assessment of efficiency was undertaken.

Poor cylinder insulation: The hot water cylinder is not properly insulated. Hot water tanks store water for long periods, and there will be a waste of energy if these tanks and the adjacent pipes are not properly insulated. This should be insulated soon.

Point-of-use: Hot water is provided by individual electric point-of-use water heaters serving individual outlets or appliances. The installation was inspected visually only. No operational testing or assessment of performance, efficiency or remaining service life was undertaken. The installation was inspected visually only. No operational testing or assessment of efficiency was undertaken.

Solar water heating: The property is provided with a solar water heating (solar thermal) system to supplement the domestic hot water supply. The installation was inspected visually only, and no operational testing or assessment of performance was undertaken. Routine maintenance should be carried out in accordance with the manufacturer's recommendations. The installation appears to have been professionally completed; however, this cannot be confirmed during a visual inspection. Your legal adviser should verify that any required Building Regulations approval, commissioning documentation and any available warranties or guarantees are provided.

Solar thermal (hot water): The property is fitted with solar thermal panels installed on the roof slope(s). These use solar energy to heat water for the domestic hot water system. No significant defects were apparent from the limited visual inspection. Routine maintenance should be carried out in accordance with the manufacturer's recommendations. The installation appears to have been professionally completed; however, this cannot be confirmed during a visual inspection. Your legal adviser should verify that appropriate planning permission (where required), Building Regulations approval, commissioning certificates and any applicable MCS certification are available (see Section **I1** – Regulations). They should also confirm whether transferable warranties or guarantees exist for the installation (see Section **I2** – Guarantees). If the necessary approvals or certification are unavailable, further investigation should be undertaken before legal purchase commitment.

Condition rating is: 1.

G6 Drainage

sample detail 4

Septic Tank: The property is connected to a septic tank. This is a private drainage system that treats foul waste before discharging the effluent to a drainage field or other approved outfall. The installation was inspected visually only, and no assessment of its operation or compliance with current environmental regulations was undertaken. The system should be regularly maintained and emptied as recommended. Your legal adviser should confirm ownership, maintenance responsibilities, any permits or exemptions, and compliance with current regulations.

Public Sewer: The property is connected to the public sewer. The drainage system is either combined (foul and surface water sharing the same pipework) or separate (foul and surface water discharged through separate pipework). Parts of the drainage system may pass through neighbouring properties or surrounding lands.

No defects noted: No significant defects requiring immediate attention were identified unless otherwise stated below. Routine maintenance appropriate to the frame material should be expected.

Inspection Chamber: The inspection chamber cover(s) were lifted where possible. No recent blockage, significant defect and sample detail 4 was noted. The chambers should be inspected periodically to ensure they remain free flowing.

Shared Drainage: It is assumed that parts of the underground drainage system are shared with neighbouring property or properties. Your legal adviser should confirm your rights and responsibilities for maintenance and repair. Your legal adviser should confirm your responsibilities for the maintenance and repair of any shared drainage system.

Soil and Vent Pipe: The soil and vent pipe is visible at the front, side and sample detail 4 of the property and is constructed of cast iron, asbestos cement and sample detail 4 material.

Drainage Repair

Inspection Chamber Cover: The inspection chamber cover(s) are broken, corroded and sample detail 4 and presents a safety hazard. It should be repaired or replaced without delay. The inspection chamber cover presents a safety hazard and should be repaired or replaced.

Inspection Chamber Walls: The inspection chamber walls are crumbling, damaged and sample detail 4. Repairs are recommended to prevent debris from entering and obstructing the drainage system.

Soil and Vent Pipe Defects: The soil and vent pipe is cracked, corroded, leaking, inadequately supported and sample detail 4. Repairs are recommended. Depending on its condition, replacement with a modern plastic system may be more economical.

Tree Root Ingress: Tree roots were noted within the inspection chamber, indicating defects in the underground drainage system. If left untreated, root ingress is likely to worsen and cause recurring blockages. A suitably qualified drainage contractor should investigate and recommend repairs.

Gullies: The above-ground rainwater and waste pipes discharge into gullies connected to the underground drainage system. The gullies are partly blocked, uncovered, completely blocked and sample detail 4. They should be cleared and repaired, as necessary. Blocked gullies can result in overflowing water and dampness to adjacent walls.

Inspection of the accessible inspection chamber(s) cannot confirm the condition of the concealed drainage system. Hidden defects may still be present and can only be identified by specialist testing, such as a CCTV drain survey.

Condition rating is: 3.

G7 Common Services

Description: Communal services and installations, including shared drainage, grounds maintenance, lifts, communal heating, hot water systems, door entry systems, parking areas and sample detail 4 were not specifically assessed as part of this inspection. These installations are normally subject to maintenance contracts. Your legal adviser should confirm that appropriate maintenance arrangements are in place and establish your responsibilities for any associated service charges or future repair costs.

Condition rating is: 2.

I Issues

I1 Regulation

The comments below are based solely on a visual inspection of the property and should not be regarded as legal advice. Your legal adviser should make appropriate enquiries and obtain supporting documentation where necessary. Your legal adviser should investigate and confirm the following, where applicable:

New Build Property: Your legal adviser should confirm whether the property benefits from a recognised new home warranty (such as NHBC, LABC, Premier Guarantee or equivalent), the remaining period of cover, the extent of the protection provided, and whether all relevant completion certificates and warranty documentation are available.

Roof Alterations and Loft Conversions – Whether roof replacements, structural roof alterations or loft conversions have the necessary statutory approvals and completion certificates.

Converted Building: The property forms part of a building that has been converted from its original use into residential accommodation. Your legal adviser should confirm that the conversion and any subsequent alterations received the necessary Planning Permission (where required), Building Regulation approval, and Completion Certificate. They should also confirm that any associated guarantees, warranties, and statutory documentation are available and advise on any implications for the property's value, marketability, and mortgageability.

Chimney Breast Alterations – Whether the removal or alteration of chimney breasts received Building Regulation approval and any required structural certification.

Electrical Installation – Whether a recent Electrical Installation Condition Report (EICR) is available.

Gas Installation – Whether recent gas safety inspections and servicing records are available.

Asbestos – Whether asbestos surveys or asbestos management information are available where asbestos-containing materials are suspected.

Flood Risk – Environmental searches to establish flood risk and any previous flooding.

Trees – Whether Tree Preservation Orders, Conservation Area restrictions or other legal constraints apply.

Rights of Way and Easements – Rights of access, easements, wayleaves, covenants, and any other rights affecting the property.

Boundaries – Boundary ownership and maintenance responsibilities from the title documentation.

Drainage – The drainage arrangement, maintenance responsibilities, and compliance with current regulations where applicable.

Leasehold Property – Remaining lease term, ground rent, service charges, reserve fund contributions, planned major works, lease restrictions and repair obligations.

Freehold Property – Any restrictive covenants, estate charges or management arrangements affecting the property.

Listed Building: The property may be a listed building. Your legal adviser should confirm its listed status, the grade of listing, and explain the legal implications of ownership. Listed buildings are subject to statutory protection, and alterations, extensions, repairs, or demolition may require Listed Building Consent and, where applicable, Planning Permission. Repairs may also need to be carried out using traditional materials and specialist contractors, which can increase maintenance and repair costs.

I2 Guarantees

Window/doors: Replacement windows and external doors (including FENSA, CERTASS or Building Regulation certification).

Boiler: Boiler installations, servicing, commissioning documentation, and heating system warranties.

Structural alterations: Structural alterations, roof replacements, loft conversions and associated structural calculations or guarantees.

DPC treatment: Damp-proofing treatment works, including treatment specifications and contractor details.

Cavity insulation: Cavity wall insulation installation certificates, guarantees, and warranties.

Spray foam: Spray foam insulation installation details, guarantees and warranties, together with confirmation of any lender requirements.

Renewable energy: Renewable energy installations, including solar PV, solar thermal, battery storage, air source heat pumps, and ground source heat pumps, together with installation certificates, ownership details, maintenance agreements, warranties and any lease or finance agreements.

Others: Any other significant repair, improvement, or structural work where guarantees, warranties or certification are available.

I3 Other Matters

Leasehold Property: Your legal adviser should also confirm the amount of any ground rent, service charges, reserve fund contributions, and whether these are reasonable. They should investigate the lease for any onerous covenants, restrictions, or unusual obligations that could affect the property's value, marketability, or future sale. Enquiries should be made of the landlord or managing agent to establish whether there are any outstanding service charges, planned major works, disputes, or significant future expenditure. Confirmation should also be obtained that appropriate buildings insurance and management arrangements are in place.

Share of Freehold Property: Where the property is held with a share of the freehold, your legal adviser should confirm the ownership structure, the remaining lease term, rights and obligations under the lease, responsibility for repairs and maintenance, service charges, reserve fund contributions, management arrangements, any restrictive covenants, and whether there are any planned major works or ongoing disputes affecting the building.

Flying Freehold: Where the property includes or is affected by a flying freehold, your legal adviser should confirm the extent of the flying freehold and ensure that adequate rights of support, shelter, protection, access for inspection, maintenance and repair are contained within the title. They should also confirm that there are no restrictions which could adversely affect the property's marketability or mortgageability, and that suitable indemnity insurance or other legal protection is available where required.

Private Road: The property is accessed via a private road or shared access. Your legal adviser should confirm ownership, rights of access, maintenance responsibilities, and any financial obligations associated with its upkeep.

Party Wall: The property shares one or more walls or structural elements with neighbouring property. Your legal adviser should explain any legal implications, including those arising under the Party Wall etc. Act 1996, where applicable, particularly if you intend to undertake structural alterations or certain repair works.

Tenanted Property: The property appears to be, or may be, occupied by a tenant. Your legal adviser should confirm whether the property will be sold with vacant possession on completion and advise on any tenancy agreements or occupiers' rights that may affect the purchase.

General Legal Enquiries: Your legal adviser should raise any additional enquiries considered appropriate following review of this report, the contract documentation, and the property title. The matters identified above arise from a visual inspection only and are intended to assist your legal adviser during the conveyancing process. They should not be regarded as a comprehensive list of legal enquiries, and your legal adviser should make any additional investigations considered appropriate.

J Risks

Risks

This section highlights risks identified during the visual inspection that may affect the property, its occupants or future maintenance. The comments are based solely on the condition observed at the time of the inspection. The Home Survey is a visual inspection only and cannot identify every potential risk. Where appropriate, further investigation by an appropriately qualified person is recommended.

J1 Risk To Building

Structural Movement: Evidence of historic, localised, recurring and progressive movement, including possible structural was observed. Where movement appears progressive or structurally significant, further investigation by an appropriately qualified structural engineer is recommended before legal commitment.

Timber Decay: Evidence of wet rot and localised timber decay was observed. The source of moisture should be identified and repaired before remedial timber works are undertaken.

Wood-Boring Insects: Evidence of active or historic wood-boring insect activity was observed. Further investigation by an appropriately qualified timber specialist is recommended where activity appears active or widespread.

Condensation: Evidence of surface mould growth and limited ventilation was observed. Maintaining appropriate heating and ventilation should assist in reducing condensation.

Drainage: Evidence of standing water, poor surface drainage and localised ponding was observed. Maintenance or further investigation should be undertaken where necessary.

Significant subsidence: Significant cracks associated with structural movement were noted to the building, the corresponding internal walls, and the party walls. I am unable to confirm, from a single visual inspection, whether the movement is historic and stable or progressive. I recommend that you instruct a suitably qualified structural engineer to investigate the cause, extent, and current activity of the movement before you exchange contracts.

The waterproofing between the chimney stack and the roof covering is damaged or defective and is causing damp penetration to the adjoining building elements (see section E1 - Chimney Stacks).

The chimney stack(s) is leaning and the movement appears significant, and immediate action is required (see section E1 - Chimney Stacks).

One or more chimney stack(s) is in poor condition. This is a safety hazard. Further investigation and repair should be arranged immediately (see section E1 - Chimney Stacks).

One or more tiles, slates, or roof covering sections are loose, slipped, cracked, broken, or missing (see section E2 - Roof Coverings).

The surface of the roof slope(s) of the building is significantly distorted, uneven or undulating (see section E2 - Roof Coverings).

The flat roof covering is weathered, blistered, split, torn, worn, ponding, or defective and causing rainwater to penetrate the building below (see section E2 - Roof Coverings).

The roof slopes to the front, side and rear of the building appear uneven or undulating, and the adjoining wall appears distorted, cracked, bowing or leaning outwards (see section E2 - Roof Coverings).

One or more defects affecting the rainwater gutters, downpipes, associated fittings, and drainage arrangements were noted (see section E3 - Rainwater Goods).

Part of the chimney breast within the roof space has been removed, and the remaining structure is not properly supported and is at risk of collapse (see section F1 - Roof Structure).

Elevated moisture readings and associated defects to wall finishes were recorded on internal wall surfaces, suggesting the presence of rising damp. Further investigation by a suitably qualified damp and timber specialist is recommended to determine the cause and extent of the problem (see section E4 - Main Walls).

J3 Risk To People

Trip Hazards: Potential trip hazards were identified, including uneven paving, damaged steps, uneven floor surfaces, loose floor coverings, damaged decking and sample detail 4. Repairs should be undertaken to reduce the risk of injury.

Damaged Stairs: The staircase requires some repairs based upon a visual inspection. Where loose handrails, damaged balustrades or uneven treads are present, these should be repaired promptly. Also, defective guarding should be repaired without delay.

Electrical Safety: Visible defects were identified. Further inspection by a qualified electrician is recommended before legal commitment.

Gas Safety: Gas appliances and installations were not assessed. Where there is any doubt regarding their age, condition or maintenance history, inspection by a Gas Safe registered engineer is recommended before legal commitment.

Asbestos: Properties constructed before 2000 may contain asbestos-containing materials (ACMs). As a precaution, we recommend that an asbestos identification survey is carried out by a suitably qualified and licensed asbestos surveyor before purchase, particularly if you intend to undertake refurbishment, alterations, or demolition works. In addition to any asbestos-containing materials specifically referred to elsewhere in this report, other concealed or inaccessible asbestos materials may also be present. The inspection undertaken for this survey is not intended to identify or confirm the presence of asbestos. According to the Health and Safety Executive (HSE), asbestos-containing materials do not normally present a significant health risk if they are in good condition and remain undisturbed. However, if such materials are damaged, drilled, cut, or otherwise disturbed, asbestos fibres may be released, posing a health hazard and requiring specialist management or removal. Any work involving suspected asbestos-containing materials must comply with the Control of Asbestos Regulations 2012. These regulations impose strict requirements on the assessment, handling, removal, and disposal of asbestos, which can significantly increase the cost of repair, maintenance, or alteration works. If asbestos is suspected or confirmed, your legal adviser should make appropriate enquiries regarding any previous asbestos surveys, removal works, or management records relating to the property. Further advice should be obtained where refurbishment is proposed.

General Advice: The inspection identified matters requiring repair, maintenance, or further investigation. These should be considered before legal commitment and reflected in your future maintenance planning. Buildings require regular inspection and maintenance throughout their service life. Prompt attention to isolated defects will normally reduce the likelihood of more extensive deterioration and costly future repairs. Where specialist inspections have been recommended within this report, these should be obtained before legal commitment where practicable.

An aerial attached to the property is loose, rusted, damaged, dangling, other (see section E1 - Chimney Stacks).

One or more tiles, slates, or roof covering sections are loose, slipped, cracked, broken, or missing (see section E2 - Roof Coverings).

The design of one or more windows does not provide a suitable means of escape for occupants in the event of a fire (see section E5 - Windows).

Trip Hazards: Potential trip hazards were identified, including uneven paving, damaged steps, raised thresholds, uneven floor surfaces, loose floor coverings, damaged decking, other. Repairs should be undertaken to reduce the risk of injury.

The electrical system is below current standards because of observed defects, and this is a safety hazard (see section G1 - Electricity).

J2 Risk To Grounds

Sloping Ground: The property may be situated on gently sloping ground. Sloping sites are more susceptible to drainage problems, erosion, ground movement, and retaining wall issues if not properly maintained. Regular monitoring and routine maintenance of drainage systems, external ground levels, and retaining structures (where present) are recommended to help minimise future risks.

Influencing trees: There are small trees within influencing distance of the property. Where no evidence of damage was observed, no further action is required. However, where damage is evident, further investigation should be undertaken by a qualified tree specialist. Routine tree management should be carried out as necessary.

Retaining Walls: Evidence of movement, bulging, cracking, deterioration was observed. Further investigation should be undertaken where structural stability appears affected and appropriate repair or rebuild organised.

Parts of the boundary fencing to the front, rear and side garden are broken, unstable, loose in places, badly damaged, rotted in places and missing in places. Defective boundary structures should be repaired where deterioration affects stability or security.

J4 Other

Airport: The property is located close to an airport and/or flight path. Aircraft operations may result in noise and disturbance, which could affect the enjoyment, marketability, and value of the property.

Train Station: The property is located close to a railway station. Associated rail operations, passenger activity, traffic, and noise may affect the enjoyment, marketability, and value of the property.

Railway Line: The property is located close to a railway line. Passing trains may generate noise and vibration, which could affect the enjoyment, marketability, and value of the property.

Repair or improve the property

Further Investigations and Repairs: Where repairs or further investigations are recommended, you should obtain quotations from suitably qualified and reputable contractors before exchanging contracts. The results of these investigations, together with advice from your legal adviser, may influence your decision to proceed or the price you are prepared to pay. Until these enquiries have been completed, the extent and cost of any necessary remedial works cannot be confirmed. Proceeding with the purchase before obtaining this information means accepting the risk that additional defects or costs may become apparent after completion.

Capture floor/site plan sketches

K1 Valuation assumptions

Market Value: The opinion of market value reflects market conditions at the date of inspection and valuation. In some locations, limited housing supply and strong buyer demand may result in competitive bidding and prices above asking levels. Should market conditions change, or the property's condition deteriorate, its resale value may be adversely affected.

Flats: Unless confirmed otherwise by your legal adviser, the valuation has been prepared on the assumption that the property is held on a lease with an unexpired term of approximately 90 years and that there are no onerous lease terms or unusual liabilities that would adversely affect its value.

Lease Length: The lease is assumed to have a satisfactory unexpired term, and no immediate action is considered necessary. However, the value and marketability of leasehold properties diminish as the lease term reduces. Once the unexpired term approaches or falls below 80 years, the cost of extending the lease can increase significantly and the property's value and mortgageability may be adversely affected. You should seek advice on extending the lease well before it reaches this point. Your legal adviser should confirm the remaining lease term and advise on any implications before you proceed with the purchase.